

Re-Mon. Survey 1, Page 186

1998 REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
HURON COUNTY
RECORDED

For Corners in
Huron
(County)

Located in: _____ Corner Code # _____

1. Public Land survey McKinley T 17 N R 10 E F-13
T _____ R _____
G-13
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____

SURVEY &
REMONUMENTATION

11 DEC 98 9:43 A.M.

JAN 28 1999

FRANCES L. HOLDWICK
REGISTER OF DEEDS

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, James T. Meek, in a field survey on October 30, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Original Survey South Bdy. T17NR10E, 1835, Harvey Parke, D.S.

F-13 South 1/4 Corner of Section 33
Post
Lynn 13", N52°E, 8 links
Cedar 8", N52°W, 2 links

County surveyors record; iron pin
Recorded surveys: L3, P64
LCRC: none

G-13 Corner of Sections 33 and 34
Post
Beech 17", N4°W, 7 links
Beech 10", N74°E, 19 1/2 links

County surveyors record; 3/4" iron pin
Recorded surveys: L3, P64
LCRC: none

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-13 South 1/4 Corner of Section 33

Found 3/4" pipe

1' North of centerline of Berne Road
Field line bears North

Accepted as the best available evidence of the original corner position.

G-13 Corner of Sections 33 and 34

Found 1" pipe

At centerline of Berne Road
East 2.0' of Intersection with Brown Road

Accepted as the best available evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13 South 1/4 Corner of Section 33

3/4" pipe in mon box

From which:
1/2" iron bears N45°E, 30.0'
1/2" iron bears S45°E, 20.0'
1/2" iron bears S45°W, 20.0'
Tag on power pole bears N60°W, 72.0'

G-13 Corner of Sections 33 and 34

1" pipe in mon box

From which:
Tag on wood post bears N37°W, 50.9'
Tag on power pole bears N17°E, 67.8'
Road sign post bears S56°E, 79.0'
West leg of direction sign bears S25°W, 20.35'

Signed by James T. Meek
Surveyor's Michigan License No. 39089

Date December 8, 1998

APPROVED AT PEER BOARD MEETING, 11-24-98 R&B

FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS JAN 24 1998 REVISED MAR 1998

