

Re-Mon. Lick, Page 186

1998 REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
HURON COUNTY
RECORDED

For Corners in Huron (County) Located in: _____ Corner Code # _____

1. Public Land survey McKinley T 17 N R 10 E F-13 G-13

2. Property Controlling in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____

SURVEY & REMONUMENTATION 11 DEC 98 9:43 A.M.

JAN 28 1999

FRANCES L. HOLDWICK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

I, James T. Meek, in a field survey on October 30, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Original Survey South Bdy. T17NR10E, 1835, Harvey Parke, D.S.

| | | | |
|------|--|------|---|
| F-13 | South 1/4 Corner of Section 33 Post Lynn 13", N52°E, 8 links Cedar 8", N52°W, 2 links County surveyors record; iron pin Recorded surveys: L3, P64 LCRC: none | G-13 | Corner of Sections 33 and 34 Post Beech 17", N4°W, 7 links Beech 10", N74°E, 19 1/2 links County surveyors record; 3/4" iron pin Recorded surveys: L3, P64 LCRC: none |
|------|--|------|---|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

| | | | |
|------|---|------|---|
| F-13 | South 1/4 Corner of Section 33 Found 3/4" pipe 1' North of centerline of Berne Road Field line bears North Accepted as the best available evidence of the original corner position. | G-13 | Corner of Sections 33 and 34 Found 1" pipe At centerline of Berne Road East 2.0' of Intersection with Brown Road Accepted as the best available evidence of the original corner position. |
|------|---|------|---|

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| | | | |
|------|---|------|---|
| F-13 | South 1/4 Corner of Section 33 3/4" pipe in mon box From which: 1/2" iron bears N45°E, 30.0' 1/2" iron bears S45°E, 20.0' 1/2" iron bears S45°W, 20.0' Tag on power pole bears N60°W, 72.0' | G-13 | Corner of Sections 33 and 34 1" pipe in mon box From which: Tag on wood post bears N37°W, 50.9' Tag on power pole bears N17°E, 67.8' Road sign post bears S56°E, 79.0' West leg of direction sign bears S25°W, 20.35' |
|------|---|------|---|

Signed by [Signature] Date December 8, 1998
Surveyor's Michigan License No. 39089

APPROVED AT PEER BOARD MEETING, 11-24-98 R&B

FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS