

Re-Mon Liber 1, Page 184

1998 REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
HURON COUNTY
RECORDED

11 DEC 98 9:42 A.M.

FRANCES L. HOLIDICK
REGISTER OF DEEDS

For Corners in

	<u>Huron</u> (County)	Located in:	Corner Code #
1. Public Land survey	McKinley	T <u>17</u> N R <u>10</u> E	<u>J-13</u> ✓ <u>K-13</u>
		T _____ R _____	_____
		T _____ R _____	_____
		T _____ R _____	_____
2. Property Controlling in Section	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____
3. Miscellaneous	S _____	T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Register of Deeds Stamp & File Number

I, James T. Meek, in a field survey on October 30, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6			5			4			3		2	1
3													
4	7			8			9			10		11	12
5													
6	18			17			16			15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													

A. Description of original monument and accessories and/or subsequent restoration:
Original Survey South Bdy. T17NR10E, 1835, Harvey Parke, D.S.

J-13 South ¼ Corner of Section 35
Post
Hemlock 20", N81°E, 24½ links
Hemlock 11", N28½°W, 10 links

County surveyors record; iron pin
Recorded surveys: L3, P61; L4, P763
LCRC: none

K-13 Corner of Sections 35 and 36
Post
Elm 22", N47°E, 31 links
Beech 8", N32°W, 10 links

County surveyors record; none
Recorded surveys: L1, P266; L4, P763
LCRC: none

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-13 South ¼ Corner of Section 35

There is no remaining evidence of the original corner position.

K-13 Corner of Sections 35 and 36

Found 1" pipe in mon box
At intersection of Berne & Sturm Rds.

Accepted as the best available evidence of the original corner position.

SURVEY &
REMONUMENTATION

JAN 28 1999

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13 South ¼ Corner of Section 35

At proportionate distance

Set ½" iron w/cap #39089 in mon box

From which:
Tag on power pole bears N56°E, 66.4'
Tag on power pole bears N60°W, 63.8'
Tag on power pole bears S50°W, 67.9'
½" iron in mon box bears East, 35.5'

K-13 Corner of Sections 35 and 36

1" pipe in mon box

From which:
Tag on power pole bears N40°E, 62.15'
Road sign post bears S55°E, 64.55'
East leg of direction sign bears South, 33.1'
Tag on power pole bears N48°W, 53.6'

Signed by James T. Meek

Date December 8, 1998

Surveyor's Michigan License No. 39089

APPROVED AT PEER BOARD MEETING, 11-24-98 RRB

FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS, JAN. 14, 1998, REVISED MAY 1998

