

Re - Mon Liber 1, Page 184

1998 REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
HURON COUNTY
RECORDED

11 DEC 98 9:42 A.M.

FRANCES L. HOLDWICK
REGISTER OF DEEDS

For Corners in

Huron
(County)

Located in:

Corner Code #

1. Public Land survey	McKinley	T 17 N R 10 E	J-13
		T _____ R _____	K-13 ✓
		T _____ R _____	
		T _____ R _____	
2. Property Controlling in Section	S _____	T _____ R _____	
	S _____	T _____ R _____	
3. Miscellaneous	S _____	T _____ R _____	

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, James T. Meek, in a field survey on October 30, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Survey South Bdy. T17NR10E, 1835, Harvey Parke, D.S.	
J-13 South 1/4 Corner of Section 35 Post Hemlock 20", N81°E, 24 1/2 links Hemlock 11", N28 1/2°W, 10 links County surveyors record; iron pin Recorded surveys: L3, P61; L4, P763 LCRC: none	K-13 Corner of Sections 35 and 36 Post Elm 22", N47°E, 31 links Beech 8", N32°W, 10 links County surveyors record; none Recorded surveys: L1, P266; L4, P763 LCRC: none

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-13 South 1/4 Corner of Section 35 There is no remaining evidence of the original corner position.	K-13 Corner of Sections 35 and 36 Found 1" pipe in mon box At intersection of Berne & Sturm Rds. Accepted as the best available evidence of the original corner position.
------------------------------------------------------------------------------------------------------------	--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

REMONUMENTATION
JAN 28 1999
SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13 South 1/4 Corner of Section 35 At proportionate distance Set 1/2" iron w/cap #39089 in mon box From which: Tag on power pole bears N56°E, 66.4' Tag on power pole bears N60°W, 63.8' Tag on power pole bears S50°W, 67.9' 1/2" iron in mon box bears East, 35.5'	K-13 Corner of Sections 35 and 36 1" pipe in mon box From which: Tag on power pole bears N40°E, 62.15' Road sign post bears S55°E, 64.55' East leg of direction sign bears South, 33.1' Tag on power pole bears N48°W, 53.1'
--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

Signed by [Signature]
Surveyor's Michigan License No. 39089

Date December 8, 1998

APPROVED AT PEER BOARD MEETING, 11-24-98 RRB

