

Common to:  
 M13 - Caseville Twp. - T18N-R10E  
 A13 - Lake Twp. - T18N-R11E  
 A01 - Chandler Twp. - T17N-R11E

*Re-Mon. Liber 2, Page 3*

1999 REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in

<u>Huron</u> (County)	Located in:	Corner Code #
1. Public Land survey: Caseville	T 17_N_ R 10_E	M-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECORDED

DEC 28 4 18 PM '99

*Francis Holmwick*  
 REGISTER OF DEEDS  
 HURON COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

I, James T. Meek, in a field survey on October 30, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												


NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 Original survey, East Bdy. T17NR10E, 1835, Harvey Parke D.S.  
 M-1 Corner of Townships 17 and 18 North, Ranges 10 and 11 East  
 Post  
 White Ash 10", S14½°W, 74 links  
 Maple 22", N44°E, 51 links  
 County Surveyor's Record: none  
 Recorded Surveys: none  
 LCRC: none

RECORDED  
 FEB 13 2000  
 SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 M-1 Corner of Townships 17 and 18 North, Ranges 10 and 11 East  
 Found 2" pipe extending 1' above ground  
 Accepted as the best available evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 M-1 Corner of Townships 17 and 18 North, Ranges 10 and 11 East  
 2" pipe extending 1' above ground  
 From which:  
 Tag in 14" walnut bears S10°W, 36.2'  
 Tag in 24" maple bears S60°W, 53.0'  
 Tag in 14" triple maple bears N85°E, 19.4'  
 Tag in 12" maple bears S70°E, 27.6'



Signed by *James T. Meek* Date 12-21-99  
 Surveyor's Michigan License No. 39089

APPROVED AT PEER BOARD MEETING 12-16-99 RLB