

*Re-Man Liber 1, Page 183*

1998 REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
 HURON COUNTY  
 RECORDED

11 DEC 98 9:42 A.M.

FRANCES L. HOLDWICK  
 REGISTER OF DEEDS

For Corners in	Located in:	Corner Code #
<u>Huron</u> (County)		
1. Public Land survey	McKinley T 17 N R 10 E	L-13
	T _____ R _____	M-13 ✓
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous	S _____ T _____ R _____	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, James T. Meek, in a field survey on October 30, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 Original Survey South Bdy. T17NR10E, 1835, Harvey Parke, D.S.

L-13 South ¼ Corner of Section 36  
 Post  
 Lynn 8", N39°E, 35 links  
 Elm 9", N33°W, 23 links  
 County surveyors record; none  
 Recorded surveys: none  
 LCRC: none

M-13 Corner of Townships 16 and 17 North, Ranges 10 & 11 East  
 Post  
 B. Ash 22", S62°E, 36 links  
 Birch 10", S75°W, 4 links  
 County surveyors record; none  
 Recorded surveys: none  
 LCRC: none

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-13 South ¼ Corner of Section 36  
 There is no remaining evidence of the original corner position.

**SURVEY & REMONUMENTATION**

JAN 28 1999

SECTION

M-13 Corner of Townships 16 and 17 North, Ranges 10 & 11 East

Found 1" iron in mon box

At intersection of Berne & Gagetown Rds.

Accepted as the best available evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13 South ¼ Corner of Section 36  
 Set ½" iron w/cap #39089 in mon box  
 At proportionate distance

From which:  
 Tag on power pole N2°E, 49.8'  
 Fence post bears S15°E, 41.8'  
 ½" iron bears S45°W, 24.0'  
 ½" iron bears N45°W, 22.0'

M-13 Corner of Townships 16 and 17 North, Ranges 10 & 11 East

1" iron in mon box

From which:  
 Concrete row marker bears N54°E, 45.6'  
 Road sign post bears S26°E, 34.0'  
 Concrete row marker bears S47°W, 54.1'  
 Tag on power pole bears N65°W, 75.75'

Signed by James T. Meek

Date December 8, 1998

Surveyor's Michigan License No. 39089

APPROVED AT PEER BOARD MEETING, 11-24-98 R.L.B.

