

T17N, R10E

SECTION COR. 8, 9, 16+17

FOUND 3/4" X 4" IRON PIPE,

12" BELOW ROAD, E DUNN RD

N 23°15' W, 34.55 TEL. POLE

S 28° E, 68.60 TRANS. POLE

S 1° W 74.10 NE COR HOUSE

SECTION COR 19, 20, 29, +30.

FOUND 1 1/4" IRON PIPE 5" ABOVE GROUND

N 4°30' W 61.80 CENTER P.P. #DE 504065

S 20° E 70.20 18" R. OAK

SOUTH 33.0' FENCE COR.

MEANDER COR, N. LINE, SEC 17.

SET 1 X 30" IRON PIPE WITH BRASS

CAP 12" BELOW GROUND, SPIKE OVER PIPE,

PLACED ROCKS AROUND COR.

EAST 1630.20 N.E. COR, SEC 17

N 76° W 131.93 S.E. COR OLD CONC. DOCK

S 34° W 128.60 10" ASH, HORIZ. SPIKE

NORTH 33.0' E-W FENCE

MEANDER COR, EAST LINE, SEC 19

FOUND 1 1/4" IRON PIPE 3" ABOVE GROUND

PLACED ROCKS AROUND POINT

SOUTH 560.63 S.E. COR SEC 19

MEANDER COR, SOUTH LINE SEC 19

FOUND 1" AXLE SHAFT 3" ABOVE GROUND,

PLACED ROCKS AROUND POINT.

N 87° E 35.03' 11" FORKED ASH

EAST 356.57 S.E. COR. SEC. 19.

SECTION COR 16, 17, 20, +21

FOUND PLAT MONUMENT, N. EDGE ROAD

N 7°45' E 12.4' SW COR BRIDGE FLOOR

SOUTH 26.35' 30" MAPLE

MEANDER COR., SOUTH LINE, SEC 17.

FOUND 3/4" IRON PIPE, N. SHOULDER ROAD

BOAT SPIKE SET OVER PIPE, 2" BELOW SURFACE

EAST 284' E BRIDGE OVER MUD CREEK

EAST 1319' S.E. COR SEC 17

FROM SURVEY BY  
W.L. PADDISON, 3-63  
DEPT CONSERVATION MAP Y 32 B  
FOR LANDS DIVISION, SUBMERGED LANDS