

Common to: A01 - Oliver Twp. - T16N-R11E
 M01 - Winsor Twp. - T16N-R10E
 M13 - McKinley Twp. - T17N-R10E

Re-Mon Liber 1, Page 181

1998 REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 HURON COUNTY
 RECORDED

11 DEC 98 9:42 A.M.

FRANCES L. HOLIDWICK
 REGISTER OF DEEDS

For Corners in

	<u>Huron</u> (County)	Located in:	Corner Code #
1. Public Land survey	Chandler	T <u>17 N</u> R <u>11 E</u>	<u>A-13</u> ✓ <u>B-13</u>
		T _____ R _____	_____
		T _____ R _____	_____
		T _____ R _____	_____
2. Property Controlling in Section	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____
3. Miscellaneous	S _____	T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, James T. Meek, in a field survey on October 30, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 Original Survey South Bdy. T17NR11E, 1835, Harvey Parke, D.S.

<p>A-13 Corner of Townships 16 and 17 North, Ranges 10 & 11 East Post B. Ash 22", S62°E, 34 links Birch 10", S75°W, 4 links</p> <p>County surveyors record; iron shaft Recorded surveys; none No LCRC</p>	<p>B-13 South ¼ Corner of Section 31 Post Cedar 10", N86°E, 7½ links Cedar 7", N46°W, 29 links</p> <p>County Surveyors Record: none Recorded surveys; none No LCRC</p>
--	---

B. Description of corner evidence found and/or method applied in

<p>A-13 Corner of Townships 16 and 17 North, Ranges 10 & 11 East Found 1" iron in mon box At intersection of Berne & Gagetown Rds. Accepted as the best available evidence of the original corner position.</p>	<p>B-13 South ¼ Corner of Section 31 Found ½" iron in mon box At centerline of Berne Road. Accepted as the best available evidence of the original corner position.</p>
--	--


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p>A-13 Corner of Townships 16 and 17 North, Ranges 10 & 11 East 1" iron in mon box From which: Concrete row marker bears N54°E, 45.6' Road sign post bears S26°E, 34.0' Concrete row marker bears S47°W, 54.1' Tag on power pole bears N65°W, 75.75'</p>	<p>B-13 South ¼ Corner of Section 31 ½" iron in mon box From which: ½" iron bears N45°E, 25.0' ½" iron bears S45°E, 30.0' ½" iron bears S45°W, 28.0' Tag in power pole bears N60°W, 79.6'</p>
---	---

SURVEY & REMONUMENTATION

JAN 28 1999

SECTION



Signed by [Signature]

Date December 8, 1998

Surveyor's Michigan License No. 39089

FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS, JAN 28 1999

APPROVED AT PEER BOARD MEETING, 11-24-98 RRB