

Re-Monumented 1, Page 181

1998 REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
HURON COUNTY
RECORDED

11 DEC 98 9:42 A.M.

FRANCES L. HOLDWICK
REGISTER OF DEEDS

For Corners in

Huron
(County)

Located in:

Corner Code #

1. Public Land survey	Chandler T <u>17</u> N R <u>11</u> E	A-13
	T _____ R _____	B-13 ✓
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous	S _____ T _____ R _____	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, James T. Meek, in a field survey on October 30, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Original Survey South Bdy. T17NR11E, 1835, Harvey Parke, D.S.

A-13	Corner of Townships 16 and 17 North, Ranges 10 & 11 East	B-13	South ¼ Corner of Section 31
	Post		Post
	B. Ash 22", S62°E, 34 links		Cedar 10", N86°E, 7½ links
	Birch 10", S75°W, 4 links		Cedar 7", N46°W, 29 links
	County surveyors record; iron shaft		County Surveyors Record: none
	Recorded surveys; none		Recorded surveys; none
	No LCRC		No LCRC

B. Description of corner evidence found and/or method applied in

A-13	Corner of Townships 16 and 17 North, Ranges 10 & 11 East	B-13	South ¼ Corner of Section 31
	Found 1" iron in mon box		Found ½" iron in mon box
	At intersection of Berne & Gagetown Rds.		At centerline of Berne Road.
	Accepted as the best available evidence of the original corner position.		Accepted as the best available evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: JAN 28 1999

-13	Corner of Townships 16 and 17 North, Ranges 10 & 11 East	B-13	South ¼ Corner of Section 31
	1" iron in mon box		½" iron in mon box
	From which:		From which:
	Concrete row marker bears N54°E, 45.6'		½" iron bears N45°E, 25.0'
	Road sign post bears S26°E, 34.0'		½" iron bears S45°E, 30.0'
	Concrete row marker bears S47°W, 54.1'		½" iron bears S45°W, 28.0'
	Tag on power pole bears N65°W, 75.75'		Tag in power pole bears N60°W, 79.6'

igned by [Signature] Date December 8, 1998
urveyor's Michigan License No. 39089

APPROVED AT PEER BOARD MEETING, 11-24-98 RRB

FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS, JAN 28 1999

