

Re-Mon. Section 1, Page 180

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1998 REMONUMENTATION

For Corners in Huron (County) Located in: _____ Corner Code # _____

1. Public Land survey Chandler T 17 N R 11 E C-13
 T _____ R _____ D-13 ✓
 T _____ R _____
 T _____ R _____

2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
HURON COUNTY
RECORDED
11 DEC 98 9:42 A.M.
FRANCES L. HOLDWICK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, James T. Meek, in a field survey on October 30, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Original Survey South Bdy. T17NR11E, 1835, Harvey Parke, D.S.

-C-13	Corner of Sections 31 & 32 Post Cedar 7", N55½°E, 4½ links B. Ash 17", N73°W, 44 links County surveyors record; pin Recorded surveys; none No LCRC	D-13	South ¼ Corner of Section 32 Post W. Ash 14", N89°E, 35 links Lynn 12", N46°W, 42 links County Surveyors Record: iron rod Recorded surveys; none No LCRC
-------	--	------	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-13	Corner of Sections 31 & 32 Found 1" iron in mon box 10' East of intersection of Berne & Maxwell Rds. Drain runs North & South Accepted as the best available evidence of the original corner position.	D-13	South ¼ Corner of Section 32 There is no remaining evidence of the original corner position.
------	--	------	---

SURVEY & REMONUMENTATION
JAN 28 1999
SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

-13	Corner of Sections 31 & 32 1" iron in mon box From which: Tag in power pole bears N20°E, 54.3' Road sign post bears S9°W, 36.5' Road sign post bears N54°W, 46.6' ¾" iron in mon box bears West 19.6'	D-13	South ¼ Corner of Section 32 At proportionate distance Set ½" iron w/cap #39089 in mon box From which: At centerline of Berne Road Tag in power pole bears N10°W, 99.75' Fence post bears S15°W, 87.2' Telephone box bears S45°W, 70.7' ¾" iron in mon box bears West
-----	---	------	---

Signed by James T. Meek
Surveyor's Michigan License No. 39089
APPROVED AT PEER BOARD MEETING, 11-24-98 RRB

Date December 8, 1998

