

JAN 28 1999

Re-Mon. Liber 1, Page 179

SECTION

1998 REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in

	<u>Huron</u> (County)	Located in:	Corner Code #
1. Public Land survey	Chandler T	<u>17 N R 11 E</u>	<u>E-13</u>
		T <u>    </u> R <u>    </u>	<u>F-13</u> ✓
		T <u>    </u> R <u>    </u>	
		T <u>    </u> R <u>    </u>	
2. Property Controlling in Section	S <u>    </u>	T <u>    </u> R <u>    </u>	
	S <u>    </u>	T <u>    </u> R <u>    </u>	
3. Miscellaneous	S <u>    </u>	T <u>    </u> R <u>    </u>	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

STATE OF MICHIGAN  
HURON COUNTY  
RECORDED

11 DEC 98 9:41 A.M.

FRANCES L. HOLDWICK  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2			
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, James T. Meek, in a field survey on October 30, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
Original Survey South Bdy. T17NR11E, 1835, Harvey Parke, D.S.

E-13 Corner of Sections 32 & 33  
Post  
Cedar 12", N88°W, 27 links  
Lynn 16", N10°E, 17 links

County surveyors record; steel pin  
Recorded surveys; L1, P436  
No LCRC

F-13 South ¼ Corner of Section 33  
Post  
Hemlock 9", N54½°E, 34 links  
Hemlock 12", N16½°W, 4 links

County Surveyors Record: none  
Recorded surveys; none  
No LCRC

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-13 Corner of Sections 32 & 33

Found ½" iron in mon box

At intersection Berne & Farver Rds.

Accepted as the best available evidence of the original corner position.

F-13 South ¼ Corner of Section 33

Found 1" iron in mon box

Accepted as the best available evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13 Corner of Sections 32 & 33

½" iron in mon box

From which:

Road sign post bears N15 °W, 52.85'  
Tag in power pole bears N30°E, 74.4'  
Road sign post bears S20°E, 34.7'  
1" iron in mon box bears West, 4.0'

F-13 South ¼ Corner of Section 33

1" iron in mon box

From which:

Tag in power pole bears North 52.7'  
½" iron bears N45°W, 27.0'  
Fence post bears S40°E, 20.0'  
½" iron bears S45°W, 25.0'

Signed by [Signature]  
Surveyor's Michigan License No. 39089

Date December 8, 1998

APPROVED AT PEER BOARD MEETING, 11-24-98 R&B

