

Re-Mon Liber 1, Page 205

1998 REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in CHANDLER Township

<u>Huron</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>17N</u> R <u>11E</u>	K-13
	T ----- R -----	_____
	T ----- R -----	_____
	T ----- R -----	_____
2. Property Controlling in Section	S ----- T ----- R -----	_____
	S ----- T ----- R -----	_____
3. Miscellaneous Property in Sec.	S ----- T ----- R -----	_____
	S ----- T ----- R -----	_____

SURVEY &
REMONUMENTATION

JAN 28 1999

SECTION

STATE OF MICHIGAN
HURON COUNTY
RECORDED

15 DEC 98 3:29 P.M.

FRANCES L. HOLDWICK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Russell L. Brown, in a field survey on August 7, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1834 G.L.O. H. Parke D.S. ; Set post Corner Sections 35 and 36; Fir 14 N58 1/2E 15.; Fir 20 N50 1/2W 34.
County Surveyors Records; NONE
County Road Commission Records: Axle, Iron Pin in line with fence West and East.
Recorded Surveys: Liber 1, Page 524, by Stewart G. Case P.S. 15399, 3/4" Iron Pin in place; WITNESSES: Spike in W. Side P.P. ; S10°W 102.25' ; Spike in W. side of 28" Box Elder Tree, S30°W 72.0'; 1/2" Iron Pin N40°E 46.35';
Unrecorded Surveys: NONE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original corner or accessories found.

Found 5/8" Re-Rod in monument Box.

Accepted 5/8" Re-Rod in Monument Box as best evidence of original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13, SE Corner Section 35 and Southwest Corner Section 36, T17N-R11E.

Found 5/8" Re-Rod in Monument Box

WITNESSES:

N70°W 87.23' found Spike in South face White Ash
N25°E 115.05' found P.K. Nail in East Face Power Pole
S40°E 37.60' found Spike in Landscape Timber
S10°W 102.10' found Spike in West Face Power Pole

East 2621.60' to L-13, South 1/4 Corner of Section 36, T17N-R11E,
West 2631.41' to J-13, South 1/4 Corner of Section 35, T17N-R11E



Signed by Russell L. Brown
Surveyor's Michigan License No. 24588

Date DEC. 7, 1998

Peer group approved at meeting held December 8, 1998. RdB