

Re-Mon Ledger 1, Page 219

**1998 REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For Corners in MEADE Township

Huron
(County)

Located in: Corner Code #

**SURVEY &
REMONUMENTATION**

STATE OF MICHIGAN
HURON COUNTY
RECORDED

- | | | |
|------------------------------------|---------------------------|-------------|
| 1. Public Land Survey | T <u>17N</u> R <u>12E</u> | <u>A-13</u> |
| | T ----- R ----- | ----- |
| | T ----- R ----- | ----- |
| | T ----- R ----- | ----- |
| 2. Property Controlling in Section | S ----- T ----- R ----- | ----- |
| | S ----- T ----- R ----- | ----- |
| 3. Miscellaneous Property in Sec. | S ----- T ----- R ----- | ----- |
| | S ----- T ----- R ----- | ----- |

JAN 28 1999

15 DEC 98 3:32 P.M.

FRANCES L. HOLDWICK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						

I, Russell L. Brown, in a field survey on July 31, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1834 G.L.O. H. Parke D.S.; Intersected Range line 1.62' South of temporary Town Corner; Hemlock 10 N71W 7;; Hemlock 12 S88E 15
County Surveyors Records: NONE
County Road Commission Records: Iron Pin; Spike 8" Maple NW 69.60'; Spike 6" Maple NW 46.0'; Spike 8" Maple NW 71.90'; Spike 12" Maple SE 44.0'.
Recorded Surveys: NONE
Unrecorded Surveys: NONE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original corner or accessories found.

Found R.R.S. Removed R.R.S. Set 3/4" x 24" Re-Rod, Reset R.R.S. over 3/4" Re-Rod.

Accepted R.R.S. as best evidence of original Corner Position.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-13, S.W. Corner Section 31, T17N-R12E,
R.R.S. over 3/4" x 24" Re-Rod
WITNESSES:
S45°E 44.18' found Spike in Northeast Face 36" Red Maple
S70°E 97.76' found Spike in North Face 30" Stump
N45°E 35.25' set 1/2" Steel Stake
S30°W 41.32' chisled "X" in West End 18" C.M.P.

NOTE:
This corner is common with
A-1, T16N-R12E,
M-1, T16N-R11E,
M-13, T17N-R11E,

East 2620.20' to B-13, South 1/4 Corner Section 31, T17N-R12E
West 2621.60' to L-13, South 1/4 Corner Section 36, T17N-R11E

Signed by Russell L. Brown
Surveyor's Michigan License No. 24588

Date DEC. 7, 1998

Peer group approved at meeting held December 8, 1998. *RLB*