

Re-mon Liber 1, Page 221

1998 REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in MEADE Township

Huron  
(County)

Located in:

Corner Code #

SURVEY &  
REMONUMENTATION

STATE OF MICHIGAN  
HURON COUNTY  
RECORDED

- 1. Public Land Survey T 17N R 12E C-13
- T ----- R -----
- T ----- R -----
- T ----- R -----
- 2. Property Controlling S \_\_\_\_\_ T ----- R -----  
in Section S \_\_\_\_\_ T ----- R -----
- 3. Miscellaneous S \_\_\_\_\_ T ----- R -----  
Property in Sec. S \_\_\_\_\_ T ----- R -----

JAN 28 1999

SECTION

15 DEC 98 3:32 P.M.

FRANCES L. HOLDWICK  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Russell L. Brown, in a field survey on July 24, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:  
 1834 G.L.O. H. Parker D.S. Set post Corner Sections 31 and 32, Beech 14 N64 1/2E 13 1/2; Hemlock 7 N68W 27;  
 County Surveyors Records: NONE  
 County Road Commission Records: Iron Pin; Spike in Telephone Pole, N30°E 65.0'; Iron Pin by Tree, S70°W 95.90';  
 Iron Pin, N68°W 67.60' Colfax Pin West 26.0'  
 Recorded Surveys: NONE  
 Unrecorded Surveys: NONE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 No evidence of original corner or accessories found.

Found 3/4" Re-Rod in Monument Box

Accepted found 3/4" Re-Rod in Monument Box as best evidence of original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-13, Corner Sections 31 and 32, T17N-R12E  
 Found 3/4" Re-Rod in Monument Box

WITNESSES:

S30°E 44.52' Set P.K. Nail in Northeast Face of Telephone Pole  
 N30°E 65.50' found Spike in West Face of Telephone Pole  
 N45°W 71.37' found Spike in East Face Power Pole  
 S55°W 63.24' Set "X" chisled in Re-Rod in Right of Way Marker

East 2643.39' to D-13, South 1/4 Corner of Section 32, T17N-R12E  
 West 2617.59' to B-13, South 1/4 Corner of Section 31, T17N-R12E



Signed by Russell L. Brown  
 Surveyor's Michigan License No. 24588

Date DEC. 7, 1998

Peer group approved at meeting held December 8, 1998. RRB