

Re-Mon Liber 1, Page 222

1998 REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in MEADE Township

Huron  
(County)

Located in:

Corner Code #

SURVEY &  
REMONUMENTATION

STATE OF MICHIGAN  
HURON COUNTY  
RECORDED

- 1. Public Land Survey T 17N R 12E D-13  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

JAN 28 1999

15 DEC 98 3:32 P.M.

SECTION

FRANCES L. HOLDWICK  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Russell L. Brown, in a field survey on July 24, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
1834 G.L.O. H. Parke D.S. Set quarter Section Post; Sugar 12 N58 1/2E 37.; Aspen 5 N58W 16 1/2  
County Surveyors Records: NONE  
County Road Commission Records: NONE  
Recorded Surveys: NONE  
Unrecorded Surveys: NONE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
No evidence of original corner or accessories found.

Set 1/2" x 18" Re-Rod capped 24588, by single proportionate measurement between C-13 and E-13

Accepted single proportionate measurement as best evidence of original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13, South 1/4 Corner of Section 32, T17N-R12E  
Set 1/2" x 18" Re-Rod capped 24588  
WITNESSES:  
N15°W 33.55' Set Spike in Northeast Corner Railroad Tie Corner Post  
N55°W 35.47' Set 1/2" x 18" Steel Stake  
S55°W 35.63' Set 1/2" x 18" Steel Stake  
S35°E 21.82' Set 1/2" 18" Steel Stake

East 2643.39' to E-13, Corner Sections 32 and 33, T17N-R12E  
West 2643.39' to C-13, Corner Sections 31 and 32, T17N-R12E

Signed by Russell L. Brown  
Surveyor's Michigan License No. 24588

Date DEC. 7, 1998



Peer group approved at meeting held December 8, 1998. R.L.B.