

Re-Mon Liber 1, Page 227

1998 REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
HURON COUNTY  
RECORDED

For Corners in MEADE Township

Huron  
(County)

Located in: Corner Code #

- 1. Public Land Survey      T 17N R 12E      I-13  
                                   T ----- R -----  
                                   T ----- R -----  
                                   T ----- R -----
- 2. Property Controlling    S ----- T ----- R -----  
    in Section               S ----- T ----- R -----
- 3. Miscellaneous           S ----- T ----- R -----  
    Property in Sec.         S ----- T ----- R -----

SURVEY &  
REMONUMENTATION

15 DEC 98 3:33 P.M.

JAN 28 1999

FRANCES L. HOLDWICK  
REGISTER OF DEEDS

SECTION

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		6		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Russell L. Brown, in a field survey on July 24, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1834 G.L.O. H. Parke D.S. Set Post Corner Sections 34 and 35, Hemlock 10 N81E 12 1/2; Hemlock 13 N70 1/2W 27  
 County Surveyors Records: NONE  
 County Road Commission Records: NONE  
 Recorded Surveys: April 18, 1977, Liber 2, Page 218 by Stewart G. Case, P.S. 15399, 3/4" Iron Pin in Place,  
 WITNESSES: Spike in Northeast Side Telephone Pole, N50°E 46.64'; Spike in Southeast Side Power Pole, S40°W 71.22'; North Post of Bridge load limit sign, S70°E 57.48'.  
 Unrecorded Surveys: NONE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original corner or accessories found.

Found 3/4" Re-Rod

Accepted found 3/4" Re-Rod as best evidence of original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13, Southwest Corner Section 35 and Southeast Corner Section 34, T17N-R12E

Found 3/4" Re-Rod

WITNESSES:

N45°E 60.20' found P.K. Nail in Southeast Face of Fence Post  
 S50°W 71.22' found Spike in East Face Power Pole  
 S60°E 41.44' to "V" Notch in South End 24" C.S.P.  
 South 45.22' to "V" Notch in East End 18" C.S.P.

East 2618.96' to J-13, South 1/4 Corner of Section 35, T17N-R12E

West 2611.68' to H-13, South 1/4 Corner of Section 34, T17N-R12E



Signed by Russell L. Brown  
Surveyor's Michigan License No. 24588

Date DEC 7, 1998

Peer group approved at meeting held December 8, 1998. RLB