

Re-Mow Lib 1, Page 212

1998 REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in LINCOLN Township

<u>Huron</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>17N</u> R <u>13E</u>	C-13
	T ----- R -----	_____
	T ----- R -----	_____
	T ----- R -----	_____
2. Property Controlling in Section	S _____ T ----- R -----	_____
	S _____ T ----- R -----	_____
3. Miscellaneous Property in Sec.	S _____ T ----- R -----	_____
	S _____ T ----- R -----	_____

SURVEY &
REMONUMENTATION

JAN 28 1999

SECTION

STATE OF MICHIGAN
HURON COUNTY
RECORDED

15 DEC 98 3:31 P.M.

FRANCES L. HOLMICK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Russell L. Brown, in a field survey on July 17, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1834 G.L.O. H. Parke D.S. Set Post corner Sections 31 and 32, Birch 11 N44W 11.; Tamarac 17 N54E 18;
County Surveyors Records: NONE
County Road Commission Records: NONE
Recorded Surveys; March 7, 1974, Liber 2, Page 50, by Stewart G. Case P.S. 15399, No object or accessories given.
Unrecorded Surveys: NONE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
No evidence of original corner or accessories found.

Found 3/4" Re-Rod

Accepted found 3/4" Re-Rod as best evidence of original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
C-13, Southwest Corner of Section 32 and Southeast Corner Section 31, T17N-R13E.

Found 3/4" Re-Rod

WITNESSES:

N65°E 63.75' cut "V" Notch in West End 12" C.M.P.
S75°W 153.20' Set Spike in North Face Power Pole
N75°E 117.95' cut "V" Notch in North End 24" C.M.P.
South 33.60' set 1/2" x 18" Re-Rod

East 2632.14' to D-13, South 1/4 Corner of Section 32, T17N-R13E
West 2632.81' to B-13, South 1/4 Corner of Section 31, T17N-R13E



Signed by Russell L. Brown
Surveyor's Michigan License No. 24588

Date DEC. 7, 1998

Peer group approved at meeting held December 8, 1998. R&B