

Re-Mon Liber 1, Page 213

1998 REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in LINCOLN Township

Huron
(County)

Located in:

Corner Code #

SURVEY &
REMONUMENTATION

STATE OF MICHIGAN
HURON COUNTY
RECORDED

15 DEC 98 3:31 P.M.

FRANCES L. HOLDWICK
REGISTER OF DEEDS

- 1. Public Land Survey T 17N R 13E D-13
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

JAN 28 1999

SECTION

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Russell L. Brown, in a field survey on July 17, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1834 G.L.O. H. Parke D.S. Set quarter Section post; Hemlock 28 N61 1/2E 30;; Beech 12 N45W 16;
County Surveyors Records: NONE
County Road Commission Records: Iron Pin; Spike in Telephone Pole, N02°W 51.15"; in line with fence North.
Recorded Surveys; NONE
Unrecorded Surveys: NONE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
No evidence of original corner or accessories found.

Found 3/4" Re-Rod

Accepted found 3/4" Re-Rod as best evidence of original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13, South 1/4 Corner of Section 32, T17N-R13E
Found 3/4" Re-Rod
WITNESSES:
North 33.43' found spike in East face of Corner Post
N25°W 73.92' set Spike in West Face of Red Maple
S50°E 101.02' set P.K. Nail in Northeast Face of Power Pole
N80°E 153.70' set Spike in South Face 30" Maple

East 2635.61' to E-13, Southeast Corner Section 32, T17N-R13E
West 2632.14' to C-13, Southwest Corner Section 32, T17N-R13E



Signed by Russell L. Brown
Surveyor's Michigan License No. 24588

Date DEC. 7, 1998

Peer group approved at meeting held December 8, 1998. R.L.B.