

Re-Mon Leher 1, Page 2/4

1998 REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in LINCOLN Township

<u>Huron</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>17N</u> R <u>13E</u>	E-13
	T ----- R -----	_____
	T ----- R -----	_____
	T ----- R -----	_____
2. Property Controlling in Section	S ----- T -----	_____
	S ----- T -----	_____
3. Miscellaneous Property in Sec.	S ----- T -----	_____
	S ----- T -----	_____

SURVEY &
REMONUMENTATION

JAN 28 1999

SECTION

STATE OF MICHIGAN
HURON COUNTY
RECORDED

15 DEC 98 3:31 P.M.

FRANCES L. HOLDWICK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Russell L. Brown, in a field survey on July 17, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1834 G.L.O. H. Parke D.S. Set Post corner Sections 32 and 33; Aspen 14 N27E 17; Birch 11 N72W 25
County Surveyors Records; NONE
County Road Commission Records: No monument stated, 33 Southwest 56.10' East of Verona Pin; Spike in Power Pole, S45°W 77.10'; Spike in Telephone Pole, N20°E 57.40'
Recorded Surveys: NONE
Unrecorded Surveys: NONE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original corner or accessories found.

Set 1/2" x 18" Steel Stake 56.10', East of found 3/4" Re-Rod at apparent corner Sections 4 and 5, T16N-R13E.

Accepted as best evidence of original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13, Southwest Corner Section 33 and Southeast Corner Section 32, T17N-R13E

Set 1/2" x 18" Steel Stake capped 24588

WITNESSES:

N45°E 30.33' Set 1/2" x 18" Steel Stake
S15°W 27.00' cut Notch in West End 12" C.M.P.
S70°W 122.51' Set Spike in Southeast Side Power Pole
N40°W 53.76' Set Spike in Wood Post

East 2614.36' to F-13, South 1/4 Corner Section 33, T17N-R13E

West 2635.61' to D-13, South 1/4 Corner Section 32, T17N-R13E

Signed by Russell L. Brown

Surveyor's Michigan License No. 24588

Date Dec. 7, 1998



Peer group approved at meeting held December 8, 1998. RXB