

Re-Mon Liber 1, Page 215

1998 REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in LINCOLN Township

| | | |
|---------------------------------------|---------------------------|---------------|
| <u>Huron</u> (County) | Located in: | Corner Code # |
| 1. Public Land Survey | T <u>17N</u> R <u>13E</u> | <u>F-13</u> |
| | T ----- R ----- | _____ |
| | T ----- R ----- | _____ |
| | T ----- R ----- | _____ |
| 2. Property Controlling in Section | S _____ T ----- R ----- | _____ |
| | S _____ T ----- R ----- | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T ----- R ----- | _____ |
| | S _____ T ----- R ----- | _____ |

SURVEY &
REMONUMENTATION

JAN 28 1999

SECTION

STATE OF MICHIGAN
HURON COUNTY
RECORDED

15 DEC 98 3:31 P.M.

FRANCES L. HOLDWICK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

I, Russell L. Brown, in a field survey on July 17, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1834 G.L.O. H. Parke D.S. Set quarter Section Post; Maple 28 N73 1/2W 16; Birch 11 N72W 25, Cedar 8 N20E 13 1/2;
County Surveyors Records: NONE
County Road Commission Records: Boat Spike in Line Fence North. Corner Fence Post, North 25.80';
Recorded Surveys: Over
Unrecorded Surveys: NONE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
No evidence of original corner or accessories found.

Set 1/2" x 18" Re-Rod with cap 24588, 43.50 feet East of 3/4" Re-Rod found at apparent North 1/4 Corner of Section 4, T16N-R13E, as per Case recorded surveys cited in Section A above. This location falls in line with the centerline of an existing ditch to the North.

Accepted as best evidence of original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13, South 1/4 Corner Section 33, T17N-R13E
Set 1/2" x 18" Re-Rod capped 24588
WITNESSES:
S45°W 55.12' set P.K. Nail in North Side Wood Corner Post
S40°E 69.52' set P.K. Nail in Northeast Side Power Pole
N40°E 29.01' set 1/2" Steel Stake
N45°W 29.85' set 1/2" Steel Stake

East 2648.26' to G-13, Southeast Corner Section 33, T17N-R13E
West 2614.36' to E-13, Southwest Corner Section 33, T17N-R13E



Signed by Russell L. Brown
Surveyor's Michigan License No. 24588

Date DEC. 7, 1998

Peer group approved at meeting held December 5, 1998. RFB

Liber 1, Page 215 A

Recorded Surveys: F-13 Lincoln

Liber 2, Page 146, Stewart G. Case P.S. 15399
South ¼ Corner Section 33, T17N-R13E, Lincoln Township,
Nothing in Place. The above survey shows South ¼ Corner Section 33 position to be 43.50 feet East of a
¾" Iron Pin at the apparent North ¼ Corner of Section 4, T16N-R13E;

October 11, 1974, Liber 2, Page 241, by Stewart G. Case P.S. 15399
South ¼ Corner Section 33, T17N-R13E, Lincoln Township,
Nothing in place
The above survey shows South ¼ Corner of Section 33 position to be 43.50 feet East of a ¾" Iron Pin at the
apparent North ¼ Corner of Section 4, T16N-R13E;

\$ 9.00 SURVEY
\$ 2.00 MSSR

SURVEY &
REMONUMENTATION

JAN 28 1999

SECTION