

Re Mon Ledger 1, Page 216

1998 REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in LINCOLN Township

<u>Huron</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>17N</u> R <u>13E</u>	<u>G-13</u>
	T ----- R -----	_____
	T ----- R -----	_____
	T ----- R -----	_____
2. Property Controlling S _____ T ----- R -----		_____
in Section S _____ T ----- R -----		_____
3. Miscellaneous S _____ T ----- R -----		_____
Property in Sec. S _____ T ----- R -----		_____

SURVEY &  
REMONUMENTATION

JAN 28 1999

SECTION

STATE OF MICHIGAN  
HURON COUNTY  
RECORDED

15 DEC 98 3:31 P.M.

FRANCES L. HOLWICK  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Russell L. Brown, in a field survey on July 17, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6			5		4		3		2			
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
1834 G.L.O. H. Parke D.S. Set Post Corner Sections 33 and 34, Birch 18 N78 1/2E 13 1/2; Cedar 14 N78W 20;  
County Surveyors Records: NONE  
County Road Commission Records: 63.36' East of Verona 3 N.W.  
Recorded Surveys: Over  
Unrecorded Surveys: NONE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
No evidence of original corner or accessories.

Found 1/2" Re-Rod raising 1" Square Iron Shaft.

Accepted found 1/2" Re-Rod over 1" Square Iron Shaft as best evidence of original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
G-13, Southwest Corner Section 34 and Southeast Corner Section 33, T17N-R13E  
Found 1/2" Re-Rod over 1" Square Iron Shaft  
WITNESSES:

N40°E 56.24' found Spike in Fence Post  
S30°E 61.00' found P.K. Nail in power Pole  
S80°W 106.50' Rivet in 18" C.M.P.  
N55°W 63.75' Top of Telephone Pedistel

East 2642.32' to H-13, South 1/4 Corner of Section 34, T17N-R13E,  
West 2648.26' to F-13, South 1/4 Corner of Section 33, T17N-R13E,



Signed by Russell L. Brown  
Surveyor's Michigan License No. 24588

Date DEC. 7, 1998

Peer group approved at meeting held December 8, 1998. RLB

*Liber 1, Page 216 A*

Recorded Surveys: G-13, Lincoln

Liber 2, Page 146, by Stewart G. Case P.S. 15399

1" Square Iron Shaft in place

Spike in Northwest Side of Fence Post, N50°E 52.25'

Spike in Northeast Side of Power Pole, S20°E 65.60'

Spike in West Side of Cedar Post, S25°W 34.40'

October 11, 1974, Liber 2, Page 241, by Stewart G. Case P.S. 15399

1" Square Iron Shaft in Place

Spike in Northwest Side of Fence Post N50°E 52.25'

Spike in Northeast Side of Power Pole, S20°E 65.60';

Spike in West Side of Cedar Post, S25°W 34.40'

\$ 9.00 SURVEY

\$ 2.00 MSSR

SURVEY &  
REMONUMENTATION

JAN 28 1999

SECTION