

Re-Now Liber 1, Page 218

1998 REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in LINCOLN Township

|                                       |                           |               |
|---------------------------------------|---------------------------|---------------|
| <u>Huron</u><br>(County)              | Located in:               | Corner Code # |
| 1. Public Land Survey                 | T <u>17N</u> R <u>13E</u> | <u>I-13</u>   |
|                                       | T _____ R _____           | _____         |
|                                       | T _____ R _____           | _____         |
|                                       | T _____ R _____           | _____         |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____   | _____         |
|                                       | S _____ T _____ R _____   | _____         |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____   | _____         |
|                                       | S _____ T _____ R _____   | _____         |

SURVEY &  
REMONUMENTATION

STATE OF MICHIGAN  
HURON COUNTY  
RECORDED

JAN 28 1999

15 DEC 98 3:32 P.M.

SECTION

FRANCES L. HOLDWICK  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Russell L. Brown, in a field survey on July 17, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

|    |    |    |    |    |    |    |   |   |   |   |   |   |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A  | B  | C  | D  | E  | F  | G  | H | I | J | K | L | M |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1834 G.L.O. H. Parke D.S. Set Post Corner Sections 34 and 35; Beech 12 N81 1/2E 17; Sugar 10 N44W 35; County Surveyors Records NONE  
County Road Commission Records; 35SW, Iron Pin in centerline of Grade North and East; Spike Corner Fence Post S15°W 26.0'; Spike in Telephone Pole, S01°W 46.30'; Spike in Corner of Fence Post; N45°E 42.50'; Spike in Telephone Pole; N80°W 92.0  
Recorded Surveys: August 17, 1977, Liber 3, Page 515, by Stewart G. Case P.S. 15399; No Marker Stated: No Witnesses given.  
Unrecorded Surveys: November 7, 1983, by Stewart G. Case P.S. 15399, Found 3/4" Re-Rod; West 39.62' to 3/4" Re-Rod; N45°E 46.89' to Spike in Northwest Side of Corner Post; South 17.60' to West Leg of Road Sign.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
No evidence of original corner or accessories found.

Found 3/4" Pipe

Accepted found 3/4" Pipe as best evidence of original corner position.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
I-13, Southeast Corner of Section 34 and Southwest Corner Section 35, T17N-R13E

Found 3/4" Pipe

WITNESSES:

S50°W 104.37' found Spike in Northwest Face Power Pole  
N45°W 41.03' found Notch in 18" C.M.P.  
S20°W 39.49' Cut "V" Notch in 18" C.M.P.  
N50°E 46.85' found Spike in Northwest Face Fence Post

East 2647.60' to Apparent J-13, South 1/4 Corner Section 35, T17N-R13E  
West 2637.98' to H-13, South 1/4 Corner Section 34, T17N-R13E



Signed by Russell L. Brown  
Surveyor's Michigan License No. 24588

Date DEC. 7, 1998

Peer group approved at meeting held December 8, 1998. R.L.B.