

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Huron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	Bloomfield	T17N R14E J-13
		T___ R___
		T___ R___
		T___ R___
2. Property Controlling in Section	S___	T___ R___
	S___	T___ R___
3. Miscellaneous Property in Sec.	S___	T___ R___
	S___	T___ R___

STATE OF MICHIGAN
 HURON COUNTY
 RECORDED

 25 NOV 98 10:05 A.M.

 FRANCES L. HOLDWICK
 REGISTER OF DEEDS

 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Charles S. Getz, in a field survey on Nov. 04, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

J-13	County Surveyor Records - NONE
1834 G.L.O., H. Parke D.S.	County Road Commission Records - NONE
Set quarter section post	Recorded Surveys - Survey Liber 3, Page 601, 1/2" Re-Rod
B. Ash 12", N69°E, 16 Links	Unrecorded Surveys - NONE
Elm 24", N58½°W, 26½ Links	

L.C.R.C. - NONE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-13
 S 1/4 Cor, Section 35, T17N-R14E
 Found 1/2" Iron Bar
 Accepted as the best available evidence of original corner position
 (On Rapson Road)


SURVEY &
 REMONUMENTATION

JAN 28 1999

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13
 S 1/4 Cor, Section 35, T17N-R14E
 Found 1/2" Iron Bar
 S35°E 57.63' to Nail in Power Pole
 S30°E 41.0' to East End of C.M.P.
 S25°W 33.30' to West End of C.M.P.
 West 2629.76' to SW Cor, Sec 35, T17N-R14E
 East 2630.04' to SE Cor, Sec 35, T17N-R14E



Signed by Charles S. Getz
 Surveyor's Michigan License No. 25843

Date November 8, 1998

PEER GROUP APPROVED AT
 MEETING 11-24-98 RLB