

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Huron</u>	Located In:	Corner Code #	
(County)			
1. Public Land Survey	Bloomfield	T 17N R 14E	L-13
		T ___ R ___	_____
		T ___ R ___	_____
		T ___ R ___	_____
2. Property Controlling in Section	S ___	T ___ R ___	_____
	S ___	T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___	T ___ R ___	_____
	S ___	T ___ R ___	_____

STATE OF MICHIGAN
HURON COUNTY
FILED
25 NOV 98 10:05 A.M.
FRANCES L. HOLDWICK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Charles S. Getz, in a field survey on Nov. 04, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

L-13	County Surveyor Records - NONE
1834 G.L.O., H. Parke D.S.	County Road Commission Records - Iron Pin in Post outline Stones Around
Set quarter section post	
Cedar 16", N71°E, 30 Links	Recorded Surveys - NONE
Hemlock 20", N42°W, 36 Links	Unrecorded Surveys - NONE

L.C.R.C. - NONE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-13
S 1/4 Cor, Section 36, T17N-R14E
Found 3/4" Iron Bar
Accepted as the best available evidence of original corner position
(On Rapson Road)


SURVEY &
REMONUMENTATION

JAN 28 1999

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13
S 1/4 Cor, Section 36, T17N-R14E
Found 3/4" Iron Bar
North 35.85' to Nail in Fence Post
N15°W 29.20' to C.M.P.
N50°W 54.20' to C.M.P.
East 2630.00' to SE Cor, Sec 36, T17N-R14E
West 2626.64' to SW Cor, Sec 36, T17N-R14E



Signed by Charles S. Getz
Surveyor's Michigan License No. 25843

Date November 8, 1998

PEER GROUP APPROVED AT
MEETING 11-24-98 R&B