

Re Mon, Liber 1, Page 161
 REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Huron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	Bloomfield	T17N R14E M-13
		T ___ R ___
		T ___ R ___
		T ___ R ___
2. Property Controlling in Section	S ___	T ___ R ___
	S ___	T ___ R ___
3. Miscellaneous Property in Sec.	S ___	T ___ R ___
	S ___	T ___ R ___

STATE OF MICHIGAN
 HURON COUNTY
 RECORDED
 25 NOV 98 10:05 A.M.
 FRANCES L. HOLDWICK
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Charles S. Getz, in a field survey on Nov. 04, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-13 1834 G.L.O., H. Parke D.S. Post Maple 11", S12°E, 11 Links Hemlock 9", N28°W, 16½ Links	County Surveyor Records - NONE County Road Commission Records - Iron Pin in Cedar Post Recorded Surveys - Survey Liber 3, Page 597, 3/4" Steel pin in mon. box in place. Unrecorded Surveys - NONE
L.C.R.C. - NONE	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-13
SE Cor, Section 36, T17N-R14E
Found 3/4" Iron Bar in Monument Box
Accepted as the best available evidence of original corner position
(Intersection of Rapson & Finkel Roads)


SURVEY &
REMONUMENTATION

JAN 28 1999

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-13
SE Cor, Section 36, T17N-R14E
Found 3/4" Iron Bar in Monument Box
N50°W 69.0' to Nail in Power Pole
N45°E 58.70' to Buried Cable Sign
S45°E 51.55' to Road Sign
S60°W 43.40' to Stop Sign
West 2630.00' to S 1/4 Cor, Sec 36, T17N-R14E
East 2631.89' to S 1/4 Cor, Sec 31, T17N-R15E



Signed by Charles S. Getz
 Surveyor's Michigan License No. 25843

Date November 8, 1998

PEER GROUP APPROVED AT
 MEETING 11-24-98 R&B