

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Huron</u>	Located In:	Corner Code #	
(County)			
1. Public Land Survey	Rubicon	T17N R15E	B-13
		T R	
		T R	
		T R	
2. Property Controlling in Section	S	T R	
	S	T R	
3. Miscellaneous Property in Sec.	S	T R	
	S	T R	

STATE OF MICHIGAN
 HURON COUNTY
 RECORDED

25 NOV 98 10:05 A.M.

FRANCES L. HOLDWICK
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Charles S. Getz, in a field survey on Nov. 12, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	N
1													
2	6	5											
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-13	County Surveyor Records - NONE
1834 G.L.O., H. Parke D.S.	County Road Commission Records - Mon. Box
Set quarter section post	Recorded Surveys - NONE
Hemlock 10", N53°E, 13 Links	Unrecorded Surveys - NONE
Cedar 8", N48°W, 18 Links	

L.C.R.C. - NONE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-13
 S 1/4 Cor, Section 31, T17N-R15E
 Found no evidence of original corner position.
 Re-established corner position by proportionate measure from G.L.O. Notes, between C-13 and A-13 as best evidence of original corner position for B-13.
 (On Rapson Road)


**SURVEY &
 REMONUMENTATION**

JAN 28 1999

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-13
 S 1/4 Cor, Section 31, T17N-R15E
 Set 1/2" Re-Rod in Monument Box (Capped)
 N60°W 144.80' to Nail in Power Pole
 N70°W 128.05' to Telephone Box
 West 231.17' to Monument Box
 West 2631.89' to SW Cor, Sec 31, T17N-R15E
 East 2631.89' to SE Cor, Sec 31, T17N-R15E



Signed by Charles S. Getz
 Surveyor's Michigan License No. 25843

Date November 15, 1998

PEER GROUP APPROVED AT
 MEETING 11-24-98 RLB