

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Huron</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	Rubicon	<u>T17N R15E</u>	<u>J-13</u>
		T___ R___	_____
		T___ R___	_____
		T___ R___	_____
2. Property Controlling in Section	S___	T___ R___	_____
	S___	T___ R___	_____
3. Miscellaneous Property in Sec.	S___	T___ R___	_____
	S___	T___ R___	_____

STATE OF MICHIGAN
HURON COUNTY
RECORDED

25 NOV 98 10:07 A.M.

FRANCES L. HOLDWICK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Charles S. Getz, in a field survey on Nov. 18, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

J-13	County Surveyor Records - NONE
1834 G.L.O., H. Parke D.S.	County Road Commission Records - NONE
Set quarter section post	Recorded Surveys - NONE
Beech 8", N60°W, 13 Links	Unrecorded Surveys - NONE
Hemlock 7", N55°E, 20 Links	

L.C.R.C. - NONE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-13
S 1/4 Cor, Section 35, T17N-R15E
Found 3/4" Iron Bar
Accepted as the best available evidence of original corner position
(On Rapson Road)

SURVEY &
REMONUMENTATION

JAN 28 1999

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13
S 1/4 Cor, Section 35, T17N-R15E
Found 3/4" Iron Bar
N70°W 114.15' to Nail in Power Pole
S70°W 149.35' to Nail in 24" Pine Tree
N25°E 26.0' to 3" Ash Tree
West 2621.74' to SW Cor, Sec 35, T17N-R15E
East 2625.28' to SE Cor, Sec 35, T17N-R15E



Signed by Charles S. Getz
Surveyor's Michigan License No. 25843

Date November 22, 1998

PEER GROUP APPROVED AT
MEETING 11-24-98 RAB