

Re-Mon Leblu, Page 191

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
HURON COUNTY
RECORDED

11 DEC 98 9:44 A.M.

FRANCES L. HOLDWICK
REGISTER OF DEEDS

1998 REMONUMENTATION

For Corners in

Huron
(County)

Located in:

Corner Code #

SURVEY &
REMONUMENTATION

J-13

K-13 ✓

JAN 28 1999

SECTION

Register of Deeds Stamp & File Number

- 1. Public Land survey Fairhaven T 17 N R 9 E
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling in Section S _____ T _____ R _____
S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, James T. Meek, in a field survey on October 30, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Original Survey South Bdy. T17NR9E, 1835, Harvey Parke, D.S.

J-13 Meander Corner of Section 35
Post
W. Ash 11", N1°E, 1.67 chains
Willow 7", S86°E, 3.6 chains

County surveyors record; none
Recorded surveys: none
LCRC: none

K-13 Corner of Sections 35 and 36
Post
Sugar 9", N64°W, 4 links
B. Ash 8", N55°E, 38½ links

County surveyors record; none
Recorded surveys: none
LCRC: none

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-13 Meander Corner of Section 35

Found 'T' iron w/cap #39089

Accepted as the best available evidence of the original corner position.

K-13 Corner of Sections 35 and 36

Found empty mon box
CL Michigan Highway M-25 bears East, 2.0'
CL Drain bears East & West

Accepted as the best available evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13 Meander Corner of Section 35

'T' iron w/cap #39089

From which:
CL East & West drain bears North, 15.0'
Tag in 16" Ash bears East 39.0'
Tag in 12" Ash bears S36°E, 37.0'

K-13 Corner of Sections 35 and 36

Set ½" iron w/cap #39089 in mon box

From which:
Tag in guard rail post bears N17°E, 94.1'
Tag in guard rail post bears S67°E, 29.0'
Tag in guard rail post bears S21°W, 76.0'
Tag in guard rail post bears N13°W, 116.9'

Signed by [Signature]
Surveyor's Michigan License No. 39089

Date December 8, 1998

APPROVED AT PEER BOARD MEETING, 11-24-98 [Signature]

FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS

