

Re-Now L&L 1, Page 190

1998 REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in

Huron
(County)

Located in:

Corner Code #

SURVEY &
REMONUMENTATION

STATE OF MICHIGAN
HURON COUNTY
RECORDED

- 1. Public Land survey Fairhaven T 17 N R 9 E
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling in Section S _____ T _____ R _____
S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____

L-13 ✓
M-13

JAN 28 1999

SECTION

11 DEC 98 9:44 A.M.

FRANCES L. HOLDWICK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		

I, James T. Meek, in a field survey on October 30, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Original Survey South Bdy. T17NR10E, 1835, Harvey Parke, D.S.

L-13 South ¼ Corner of Section 36
Post
W. Ash 8", N63°W, 5.10 chains
No other tree near

County surveyors record: none
Recorded surveys: none
LCRC: none

M-13 Corner of Townships 16 and 17 North, Ranges 9 and 10 East
Post
Lynn 14", S47°E, 23 links
Elm 12", N37°W, 50½ links
County surveyors record: axle shaft
Recorded surveys: none
LCRC: none

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-13 South ¼ Corner of Section 36

There is no remaining evidence of original corner position

M-13 Corner of Townships 16 and 17 North, Ranges 9 and 10 East

Found ¾" iron in mon box
4' East of CL Bay Port Rd.

Accepted as the best available evidence of original corner position

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13 South ¼ Corner of Section 36

At proportionate distance

Set ½" iron w/cap #39089

From which:
CL East & West drain bears North 4'
CL Drive bears East, 18.0'
Tag in PP bears S15°W, 146.5'
4" conc post w/½" iron bears N2°W, 18.6'

M-13 Corner of Townships 16 and 17 North, Ranges 9 and 10 East

¾" iron in mon box

From which:
Tag in PP bears S70°E, 76.9'
Tag in 12" Elm bears S40°W, 58.9'
½" iron bears N45°W, 28.0'
½" iron bears N45°E, 20.0'

Signed by James T. Meek

Date December 8, 1998

Surveyor's Michigan License No. 39089

APPROVED AT PEER BOARD MEETING, 11-24-98 RLB

FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS, JAN 28, 1994
REVISED MAY 14, 1975
REVISED JAN, 1983

