

Common to: A13 - McKinley Twp. - T17N-R10E  
 A01 - Winsor Twp. - T16N-R10E  
 M01 - Fair Haven Twp. - T16N-R9E

*Re-Monumentation 1, Page 190*

1998 REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in

Huron Located in: \_\_\_\_\_  
 (County)

1. Public Land survey Fairhaven T 17 N R 9 E  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Corner Code #

L-13  
 M-13

SURVEY &  
 REMONUMENTATION

JAN 28 1999

SECTION

STATE OF MICHIGAN  
 HURON COUNTY  
 RECORDED

11 DEC 98 9:44 A.M.

FRANCES L. HOLDWICK  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, James T. Meek, in a field survey on October 30, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 Original Survey South Bdy. T17NR10E, 1835, Harvey Parke, D.S.

L-13 South 1/4 Corner of Section 36  
 Post  
 W. Ash 8", N63°W, 5.10 chains  
 No other tree near  
 County surveyors record: none  
 Recorded surveys: none  
 LCRC: none

M-13 Corner of Townships 16 and 17 North,  
 Ranges 9 and 10 East  
 Post  
 Lynn 14", S47°E, 23 links  
 Elm 12", N37°W, 50 1/2 links  
 County surveyors record: axle shaft  
 Recorded surveys: none  
 LCRC: none

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-13 South 1/4 Corner of Section 36  
 There is no remaining evidence  
 of original corner position

M-13 Corner of Townships 16 and 17 North,  
 Ranges 9 and 10 East  
 Found 1/2" iron in mon box  
 4' East of CL Bay Port Rd.

Accepted as the best available evidence  
 of original corner position

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13 South 1/4 Corner of Section 36  
 At proportionate distance  
 Set 1/2" iron w/cap #39089  
 From which:  
 CL East & West drain bears North 4'  
 CL Drive bears East, 18.0'  
 Tag in PP bears S15°W, 146.5'  
 4" conc post w/1/2" iron bears N2°W, 18.6'

M-13 Corner of Townships 16 and 17 North,  
 Ranges 9 and 10 East  
 1/2" iron in mon box  
 From which:  
 Tag in PP bears S70°E, 76.9'  
 Tag in 12" Elm bears S40°W, 58.9'  
 1/2" iron bears N45°W, 28.0'  
 1/2" iron bears N45°E, 20.0'

Signed by James T. Meek

Date December 8, 1998

Surveyor's Michigan License No. 39089

APPROVED AT PEER BOARD MEETING, 11-24-98 R&B

FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS JAN 28, 1997

