

Re-Mon. Liber 2, Page 7

For Corners in

Huron
(County)

Located in:

Corner Code #

- 1. Public Land survey: Lake T 18_N_ R 11_E F-13 ✓
T ___ R ___ G-13
T ___ R ___
T ___ R ___
- 2. Property Controlling S ___ T ___ R ___
in Section S ___ T ___ R ___
- 3. Miscellaneous S ___ T ___ R ___
Property in Sec. S ___ T ___ R ___
- 4. Lot No. _____, Recorded Plat SECTION
- 5. Private Claims _____

RECORDED

DEC 28 4 18 PM '99

Francis Hildebrand
REGISTER OF DEEDS
HURON COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

I, James T. Meek, in a field survey on October 30, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5			4		3		2		1	
3													
4	7		8			9		10		11		12	
5													
6	18		17			16		15		14		13	
7													
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey, South Bdy. T18NR11E, 1835, Harvey Parke D.S.

F-13 South ¼ Corner of Section 33
Post
Maple 26", N84½°W, 44 links
Elm 8", N59½°W, 83 links

County Surveyor's Record: none
Recorded Surveys: L3, P751
LCRC: none

G-13 Corner of Sections 33 and 34
Post
Hemlock 13", N53½°E, 15 links
Sugar 18", N82°W, 24 links

County Surveyor's Record: Lake pin 21.8' West of Chandler pin
Recorded Surveys: L3, P751
LCRC: none

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-13 South ¼ Corner of Section 33

Found ¾" iron in mon box

Occupation line bears North

Accepted as the best available evidence of the original corner position.

G-13 Corner of Sections 33 and 34

Found no evidence of the original corner position.

Set ½" iron in mon box at record offset from corner of Sections 3 & 4 T17N-R11E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13 South ¼ Corner of Section 33

¾" iron in mon box

From which:
½" iron bears N45°E, 30.0'
Fence post bears N20°W, 30.5'
Tag in power pole bears S65°W, 127.5'
Phone box bears N60°W, 54.4'

G-13 Corner of Sections 33 and 34

½" iron in mon box

From which:
1" iron East, 21.8'
Stop sign post bears N45°E, 46.8'
Stop sign post bears S80°E, 90.9'
Stop sign post bears S80°W, 70.1'
Tag in power pole bears N45°W, 55.5'

Signed by [Signature]

Date 12-21-99

Surveyor's Michigan License No. 39089

APPROVED AT PEER BOARD MEETING 12-16-99 RLB

