

Re-Mon. Liber 2, Page 8

1999 REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

For Corners in

Huron (County)

Located in:

Corner Code #

- 1. Public Land survey: Lake T 18_N_ R 11_E H-13
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat SECTION
5. Private Claims

Dec 28 4 10 PM '99

Francis Holbrook REGISTER OF DEEDS HURON COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

I, James T. Meek, in a field survey on October 30, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. Contains numerical values for each cell.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: Original survey, South Bdy. T18NR11E, 1835, Harvey Parke D.S.

H-13 South 1/4 Corner of Section 34 Post Cedar 13", N57°W, 14 links Hemlock 6", N66°E, 22 links

I-13 Corner of Sections 34 and 35 Post Black Ash 8, N46 1/2°E, 17 links Cedar 8", N36°W, 17 links

County Surveyor's Record: none Recorded Surveys: none LCRC: none

County Surveyor's Record: none Recorded Surveys: none LCRC: none

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13 South 1/4 Corner of Section 34 Found no evidence of the original corner position. Set 1/2" iron in mon box at record offset from the North 1/4 corner of Section 3, T17N-R11E.

I-13 Corner of Sections 34 and 35 Found 1/2" iron w/cap #15399 Accepted as the best available evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13 South 1/4 Corner of Section 34 1/2" iron in mon box From which: 1" iron in mon box bears East, 20.79' Tag in power pole bears North, 50.2' 1/2" iron bears S60°E, 23.0' 1/2" iron bears S40°W, 23.4' Tele cable post bears N70°W, 82.7'

I-13 Corner of Sections 34 and 35 1/2" iron w/cap #15399 in mon box From which: 1" iron in mon box bears East, 19.78' 1/2" iron bears S45°W, 20.0' West direct. sign post bears S10°E, 21.25' Stop sign post bears N20°W, 47.1' Tag in power pole bears N45°W, 71.7'

Signed by [Signature] Date 12-21-99 Surveyor's Michigan License No. 39089

APPROVED AT PEER BOARD MEETING 12-16-98 RLJ

