

Re Mon. Liber 2, Page 9

For Corners in

Huron  
(County)

Located in:

Corner Code #

- 1. Public Land survey: Lake T 18\_N\_ R 11\_E J-13 ✓  
T \_\_\_ R \_\_\_ K-13  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_
- 2. Property Controlling S \_\_\_ T \_\_\_ R \_\_\_  
in Section S \_\_\_ T \_\_\_ R \_\_\_
- 3. Miscellaneous S \_\_\_ T \_\_\_ R \_\_\_  
Property in Sec. S \_\_\_ T \_\_\_ R \_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

RECORDED

DEC 28 4 10 PM '99

Francis Hollemick  
REGISTER OF DEEDS  
HURON COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

SECTION

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, James T. Meek, in a field survey on October 30, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey, South Bdy. T18NR11E, 1835, Harvey Parke D.S.  
J-13 South ¼ Corner of Section 35  
Post  
Hemlock 28", N81°E, 23 links  
Hemlock 8", N72½°W, 15 links  
County Surveyor's Record: iron rod over post  
Recorded Surveys: L1, P541  
LCRC: none

K-13 Corner of Sections 35 and 36  
Post  
Birch 10", N74½°E, 27 links  
Cedar 12", N38°W, 9 links  
County Surveyor's Record: 1"sq. iron  
Recorded Surveys: none  
LCRC: none

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-13 South ¼ Corner of Section 35  
Found ¾" iron in mon box  
Occupation line bears North  
Accepted as the best available evidence of the original corner position.

K-13 Corner of Sections 35 and 36  
Found 1" pipe at intersection of Kinde & Champagne Roads  
Accepted as the best available evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13 South ¼ Corner of Section 35  
¾" iron in mon box  
From which:  
¾" iron in mon box bears East, 17.85'  
Tag in power pole bears North, 53.3'  
Tag in corner fence post bears S20°E, 37.5'  
Phone box bears N5°E, 31.0'

K-13 Corner of Sections 35 and 36  
1" pipe in mon box  
From which:  
Phone box bears N30°E, 54.6'  
Stop sign post bears S30°E, 43.1'  
½" iron bears S20°W, 35.0'  
Tag in power pole bears N50°W, 77.9'

Signed by [Signature]  
Surveyor's Michigan License No. 39089

Date 12-21-99

APPROVED AT PEER BOARD MEETING 12-16-99 R&B

