

Common to:  
 A13 - Hume Twp. - T18N-R12E  
 A01 - Meade Twp. - T17N-R12E  
 M01 - Chandler Twp. - T17N-R11E

*Re-Mon. Liked, Page 16*

1999 REMONUMENTATION

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in  
Huron  
 (County)

Located in: Corner Code #

1. Public Land survey: Lake T 18\_N\_ R 11\_E L-13  
 T \_\_\_ R \_\_\_ M-13 ✓  
 T \_\_\_ R \_\_\_  
 T \_\_\_ R \_\_\_

2. Property Controlling S \_\_\_ T \_\_\_ R \_\_\_  
 in Section S \_\_\_ T \_\_\_ R \_\_\_

3. Miscellaneous S \_\_\_ T \_\_\_ R \_\_\_  
 Property in Sec. S \_\_\_ T \_\_\_ R \_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_ SECTION \_\_\_\_\_

5. Private Claims \_\_\_\_\_

**RECORDED**

**Dec 28 4 19 PM '99**

*Frances Holmbeck*  
 REGISTER OF DEEDS  
 HURON COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

I, James T. Meek, in a field survey on October 30, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 Original survey, South Bdy. T18NR11E, 1835, Harvey Parke D.S.

L-13 South ¼ Corner of Section 36 Post Sugar 9", N82°W, 26½ links Sugar 9", N38½°E, 8½ links	M-13 Corner of Townships 17 & 18 North, Ranges 11 & 12 East Post White Ash 8", N88°W, 9 links Aspen 16", S88°E, 10 links
County Surveyor's Record: none Recorded Surveys: none LCRC: none	County Surveyor's Record: axle Recorded Surveys: L3, P289 LCRC: none

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-13 South ¼ Corner of Section 36 Found PK nail at centerline of Kinde Road. Set ½" iron in mon box. Accepted as the best available evidence of the original corner position.	M-13 Corner of Townships 17 & 18 North, Ranges 11 & 12 East Found 1¼" pipe at intersection of Grassmere and Kinde Roads Accepted as the best available evidence of the original corner position.
---	--

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13 South ¼ Corner of Section 36 ½" iron in mon box From which: Tag in power pole bears North, 54.0' No Passing Zone sign post bears N80°E, 110.0' Do Not Pass sign post bears S80°E, 108.5' ½" iron bears S45°W, 22.0'	M-13 Corner of Townships 17 & 18 North, Ranges 11 & 12 East 1¼" pipe in mon box From which: Tag in power pole bears N45°E, 85.4' Stop sign post bears S20°E, 37.0' Tag in fence post corner bears S40°W, 48.5' Stop sign post bears N30°W, 37.7'
--	--

Signed by [Signature] Date 12-21-99  
 Surveyor's Michigan License No. 39089

STATE OF MICHIGAN  
 JAMES T. MEEK  
 LAND SURVEYOR  
 LICENSED LAND SURVEYOR  
 39089  
 FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS, JAN. 28, 1981  
 REVISED MAY 20, 1985  
 REVISED JAN. 1983  
 REVISED OCT. 1995

APPROVED AT PEER BOARD MEETING 12-16-99 RLB