

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Huron

(County)	Located In:		Corner Code #1
1. Public Land Survey	T	R	
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S 20	T 18N R 11E	10
3. Miscellaneous Property in Sec.	S	T	R
4. Lot No.	Recorded Plat		
5. Private Claims			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Gary C. Bilow in a field survey on April 20, 1993, 19
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

10: Post not established by U.S. Government Survey. C.M. Cade, a Registered Civil Engineer, for a survey of the Huron State Park (now known as Sleeper State Park) in 1928 shows this corner 1310' North of corner C9 on his survey drawing. Cade called for a Cedar Stake but lists no accessories. Department of Conservation Surveyor D. Scott's (PS #12029) retracement survey in 1964 of C.M. Cade's survey shows the distance to corner C9 to be 1310.5' but does not list what was found or give any accessories. Case Surveying of Bad Axe, MI in a 1970 survey of the South 1/2 of the Southwest 1/4 of Section 20 shows "Corner post in place and the distance to corner C9 to be 1310.30".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

10: Reestablished corner on line between corners C9 and C8 at a distance of 1310.3' North of corner C9 per the 1970 survey performed by Case Surveying.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:



10: Set 1/2" x 36" rebar encased in a 4" diameter concrete cylinder and capped with a cast aluminum Michigan Department of Natural Resources Tablet 1' above ground and piled rocks around
N40E 23.96'. Nail & Tag in West side of 21" Oak
N22E 51.23'. Nail & Tag in West side of triple 15" Oak
N90E 64.54'. Nail & Tag in South side of dead 13" Birch

Signed by Gary C. Bilow
Surveyor's Michigan License No. 26453

Date July 1, 1993