

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Huron  
(County)

Located In: \_\_\_\_\_ Corner Code 77

- |                                    |   |     |       |    |
|------------------------------------|---|-----|-------|----|
| 1. Public Land Survey              | T | 18N | R 11E | C9 |
|                                    | T |     | R     |    |
|                                    | T |     | R     |    |
|                                    | T |     | R     |    |
| 2. Property Controlling in Section | S | T   | R     |    |
|                                    | S | T   | R     |    |
| 3. Miscellaneous                   | S | T   | R     |    |
| Property in Sec.                   | S | T   | R     |    |
| 4. Lot No. _____, Recorded Plat    |   |     |       |    |
| 5. Private Claims                  |   |     |       |    |

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Gary C. Bilow, in a field survey on April 20, 1993, 19\_\_\_\_ do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 C9: Post established by U.S. Deputy Surveyor H. Parke in 1835 - accessories: B. Ash 14 N33-1/2W 16 and Cedar 14 S25-1/2R 13. C.M. Cade, a Registered Civil Engineer, in 1928 performed a survey of the Huron State Park (now known as Sleeper State Park) in which he records a "Cedar Post" but lists no accessories. Department of Conservation Surveyor D. Scott's (PS #12029) retracement survey of Cade's survey in 1964 does not list what was recovered but lists accessories: N2W 39.0', 6" Box Elder; S70E 60.7', Twin 8" Poplar; S48W 49.0', Corner Fence Post. Corner recorded under Act 74 PA 1970 by L. Feindt (PS #21566) in 1981 in Liber 1 Page 41 as "Found 1" solid rod centerline Conkev Road - raised with T-iron - accessories: North-39.40'-16" Ash, S70E-61.00'-10" Poplar, and S40W- 50.25'-20" Ash". S. Case (PS #15399) on a 1983 survey records "Found steel pin - accessories: North 39.15' to spike in E. side of 15" Elder, S20W 49.0' to spike in NW side of 36" Elder, and N45E 31.45' to top center E. end 15" Concrete Tile".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 C9: Found T-iron in centerline Conkev Road at centerline Drive to South and one (1) of Feindt's witnesses and one (1) of Scott's witnesses. Accepted T-iron as the best evidence of the original GLO post.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 C9: Left T-iron in place  
 S54W 49.13', Nail & Tag in North side of corner Fence Post  
 S38W 49.81', Nail & Tag in East side of 24" Ash  
 S42E 36.60', Nail & Tag in West side of 7" Poplar  
 N1E 32.78', Center of a Telephone Box



Signed by Gary C. Bilow Date July 1, 1993  
 Surveyor's Michigan License No. 28453

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN. 1983