

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Huron
 (County)

Located In: Corner Code //

- | | | | | | |
|------------------------------------|---|-----|---|-----|----|
| 1. Public Land Survey | T | 18N | R | 11E | C8 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | T | R | | |
| | S | T | R | | |
| 3. Miscellaneous Property in Sec. | S | T | R | | |
| | S | T | R | | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, **Gary C. Bilow**, in a field survey on **April 20, 1993**, 19____ do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

C8: Post established by U.S. Deputy Surveyor H. Parke in 1835 - accessories: Pine 28 S47W 10 and B. Ash 10 N37E 49. C.M. Cade, a Registered Civil Engineer, in a survey of the Huron State Park (now known as Sleeper Stae Park) computed this location in his subdivision of Section 20 but did not set. Corner recorded under Act 74 PA 1970 by L. Feindt (PS #21566) in 1981 in Liber 1 Page 41 as "Set 1" pipe with cap #3920 using single proration between corners C9 and the Meander Corner for Sections 17 and 18 - accessories: S73W-41.96'-24" Oak, S51E-29.66'-9" Ash, N54W-39.90'-7" Maple, N12E 42.08'-8" Maple, and N81E-32.44'-1" pipe".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C8: Found 1" pipe with cap #3920 and one of Feindt's witnesses. Accepted pipe as the best evidence of the original GLO post.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**C8: Left 1" pipe with cap #3920 in place
 S76W 41.45', Nail & Tag in North side
 of 27" Oak
 N20E 8.36', Nail & Tag in East side of
 15" Oak
 S2W 26.39', Nail & Tag in East side of
 9" White Birch
 S60E 37.98', Nail & Tag in North side of
 10" Oak**



Signed by Gary C. Bilow Date 4/20/93
 Surveyor's Michigan License No. 26453