

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Re-Mon. Feb 2, Page 1

For Corners in

<u>Huron</u> (County)	Located in:	Corner Code #
1. Public Land survey: <u>Hume</u>	T 18_N_ R 12_E	D-13
	T _____ R _____	E-13 ✓
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		SECTION _____
5. Private Claims _____		

RECORDED

Dec 28 4 19 PM '99

Francis Holmick
REGISTER OF DEEDS
HURON COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

I, James T. Meek, in a field survey on October 30, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Original survey, South Bdy. T18NR12E, 1835,
Harvey Parke D.S.

D-13 South ¼ Corner of Section 32
Post
Beech 6", N21°W, 2 links
Sugar 10", N60°E, 88 links

County Surveyor's Record: cedar post
Recorded Surveys: L4, P57
LCRC: none

E-13 Corner of Sections 32 and 33
Post
Beech 16", N22°W, 27½ links
Hemlock 10", N71°E, 37 links

County Surveyor's Record: none
Recorded Surveys: L4, P57; L1, P488
LCRC: none

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-13 South ¼ Corner of Section 32
Found 1" iron in mon box at centerline of Kinde Road.
Occupation line bears North.

Accepted as the best available evidence of the original corner position.

E-13 Corner of Sections 32 and 33

Found ½" iron in mon box at intersection of Kinde & Lackie Roads

Accepted as the best available evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13 South ¼ Corner of Section 32
1" iron in mon box

From which:
1" iron in mon box bears East, 164.92'
Tag in power pole bears North, 83.4'
Tag in 14" apple bears S30°W, 66.4'
Phone box bears N70°W, 126.0'

E-13 Corner of Sections 32 and 33
½" iron in mon box

From which:
¾" iron in mon box bears East 99.01'
West direct. sign post bears South, 23.7'
Weight limit sign post bears N10°E, 81.2'
Stop sign post bears N20°W, 39.7'
Tele box bears N60°W, 101.7'

Signed by *J. Meek* Date 12-21-99
Surveyor's Michigan License No. 39089

APPROVED AT PEER BOARD MEETING 12-16-99 RLB

