

Re-Mon Liber 1, Page 237

1999 REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
HURON COUNTY
RECORDED

For corners in

<u>Huron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	Dwight	T18N R13E D-13
		T R
		T R
		T R
2. Property Controlling in Section	S	T R
	S	T R
3. Miscellaneous Property in Sec.	S	T R
	S	T R

28 OCT 99 9:11 A.M.

FRANCES L. HOLLOWICK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Charles S. Getz, in a field survey on April 12, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

D-13 1834 G.L.O., H. Parke D.S. County Road Commission Records - Cedar Post
Set quarter section post Recorded Surveys - NONE
Cedar 10", N86 1/2°E, 17 Links Unrecorded Surveys - Brown, 7-16-97, P.K. Nail
Do. 9", N42 1/2°W, 14 Links Case, 2-27-98, P.K. Nail in place.

L.C.R.C. - NONE

County Surveyor Records - NONE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-13
S 1/4 Cor, Section 32, T18N-R13E
Found P.K. Nail as per Survey by Huron Surveying, Inc. dated 7-16-97
Accepted as the best available evidence of original corner position
(On Kinde Road)

RECORDED

FEB 23 2000

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13
S 1/4 Cor, Section 32, T18N-R13E
Set 1/2" Iron Bar in Monument Box (Capped)
North 41.00' to Metal Fence Post
West 96.22' to Monument Box
N10°E 44.30' to Center of 18' Tile
N45°E 30.00' to Iron Bar
N45°W 30.00' to Iron Bar
West 2627.60' to SW Cor, Sec 32, T18N-R13E
East 2627.74' to SE Cor, Sec 32, T18N-R13E



Signed by Charles S. Getz
Surveyor's Michigan License No. 25843

Date August 14, 1999

PEER GROUP APPROVED AT MEETING
HELD October 26, 1999 R.S.B.