

1999 REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Huron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	Dwight T18N R13E	E-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
HURON COUNTY
RECORDED

28 OCT 99 9:11 A.M.

FRANCES L. HOLDWICK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Charles S. Getz, in a field survey on April 12, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
E-13 1834 G.L.O., H. Parke D.S. County Road Commission Records - 3/4" Iron Pin in Wood Post
Set Post Recorded Surveys - NONE
Cedar 20", N62°W, 19 Links Unrecorded Surveys - Brown, 7-16-97, 3/4" Re-Rod in Monument Box
Aspen 20", N81°E, 32 Links Case, 6-19-98, Iron in mon. box.

L.C.R.C. - NONE

County Surveyor Records - NONE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-13
SW Cor, Section 33, T18N-R13E
Found 3/4" Iron Bar in Monument Box
Accepted as the best available evidence of original corner position
(Intersection of Kinde & Hellems Roads)

RECORDED

FEB 20 2001

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13
SW Cor, Section 33, T18N-R13E
Found 3/4" Iron Bar in Monument Box
S50°W 83.30' to Nail in Power Pole
N45°E 48.55' to Nail in Power Pole
S55°E 48.70' to Nail in Anchor Pole
West 105.75' to Monument Box
South 20.70' to East Leg of Road Sign
West 2627.74' to S 1/4 Cor, Sec 32, T18N-R13E
East 2641.04' to S 1/4 Cor, Sec 33, T18N-R13E



Signed by Charles S. Getz
Surveyor's Michigan License No. 25843

Date August 14, 1999

PEER GROUP APPROVED AT MEETING
HELD October 26, 1999. *RAB*