

Re. Man Likew, Page 239

1999 REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
HURON COUNTY  
RECORDED

28 OCT 99 9:11 A.M.

FRANCES L. HOLDWICK  
REGISTER OF DEEDS

For corners in

Huron (County)	Located In:	Corner Code #
1. Public Land Survey	Dwight T18N R13E	F-13
	T__ R__	_____
	T__ R__	_____
	T__ R__	_____
2. Property Controlling in Section	S__ T__ R__	_____
	S__ T__ R__	_____
3. Miscellaneous Property in Sec.	S__ T__ R__	_____
	S__ T__ R__	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Charles S. Getz, in a field survey on April 12, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

F-13 1834 G.L.O., H. Parke D.S. County Road Commission Records - 3/4" Iron Pin  
 Set quarter section post Recorded Surveys - Case, 4-24-73, Liber 1, Page 438, 3/4" iron pin in place  
 Elm 26", N26°W, 25 Links  
 B. Ash 6", N75°E, 16 Links Unrecorded Surveys - Case, 6-19-98, Iron in mon. box.

L.C.R.C. - NONE

County Surveyor Records - NONE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-13  
 S 1/4 Cor, Section 33, T18N-R13E  
 Found 5/8" Iron Bar in Monument Box  
 Accepted as the best available evidence of original corner position  
 (On Kinde Road)

RECORDED  
 FEB 02 2000  
 SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13  
 S 1/4 Cor, Section 33, T18N-R13E  
 Found 5/8" Iron Bar in Monument Box  
 N10°E 38.07' to Nail in Power Pole  
 N05°W 40.50' to North End of Drain Tile  
 N70°W 110.00' to North End of Culvert  
 S70°W 131.00' to South End of Culvert  
 West 2641.04' to SW Cor, Sec 33, T18N-R13E  
 East 2624.12' to SE Cor, Sec 33, T18N-R13E



Signed by Charles S. Getz

Date August 14, 1999

Surveyor's Michigan License No. 25843

PEER GROUP APPROVED AT MEETING  
 HELD October 26, 1999 R.A.B.