

Common to:  
 A13 - Huron Twp. - T18N-R14E  
 A01 - Bloomfield Twp. - T17N-R14E  
 M01 - Lincoln Twp. - T17N-R13E

1999 REMONUMENTATION

*Re Mon Liber 1, Page 246*

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Huron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	Dwight T18N R13E	M-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN  
 HURON COUNTY  
 RECORDED  
 28 OCT 99 9:13 A.M.  
 FRANCES L. HOLDWICK  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Charles S. Getz, in a field survey on April 12, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-13 1834 G.L.O., H. Parke D.S. Post Hemlock 26", N10°E, 8 Links Fir 11", S16½°E, 32 Links	County Road Commission Records - Monument Recorded Surveys - Case, 5-9-72, Liber 1, Page 194, Mon. box Case, 8-23-78, Liber 3, Page 490, 5/8" steel pin in Mon. box Case, 8-23-78, Liber 3, Page 593, Mon. box in place. Case, 5-12-80, Liber 4, Page 289, Pin in Mon. Box in place.
L.C.R.C. - NONE	Unrecorded Surveys - NONE
County Surveyor Records - November 19th, 1901 May 11th, 1911 Surveys show Corner	


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-13  
 SE Cor, Section 36, T18N-R13E  
 Found Monument Box  
 Accepted as the best available evidence of original corner position.  
 (Intersection of Kinde and Verona Roads)

RECORDED  
 FEB 12 1999  
 SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-13  
 SE Cor, Section 36, T18N-R13E  
 Set 1/2" Iron Bar in Monument Box (Capped)  
 N45°E 61.60' to Nail in Telephone Pole  
 N45°W 58.30' to Nail in Power Pole  
 S45°E 61.40' to Nail in Telephone Pole  
 S30°W 78.80' to Northeast Corner of Building  
 S50°W 80.15' to Northwest Corner of Building  
 West 2630.18' to S 1/4 Cor, Sec 36, T18N-R13E  
 East 2500.47' to S 1/4 Cor, Sec 31, T18N-R14E



Signed by Charles S. Getz  
 Surveyor's Michigan License No. 25843

Date August 14, 1999

PEER GROUP APPROVED AT MEETING  
 HELD October 26, 1999 R.A.B.