

Re Mon Liber 1, Page 251

1999 REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
HURON COUNTY
RECORDED

28 OCT 99 9:14 A.M.

FRANCES L. HOLDWICK
REGISTER OF DEEDS

For corners in

<u>Huron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	Huron	T18N R14E E-13
2. Property Controlling in Section	S	T R
3. Miscellaneous Property in Sec.	S	T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Charles S. Getz, in a field survey on April 14, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

E-13 1834 G.L.O., H. Parke D.S. County Road Commission Records - Iron Pin in Cedar Post Set Post
 B. Ash 14", N31°E, 30 Links Recorded Surveys - NONE
 Do. 12", N44°W, 35 Links
 Unrecorded Surveys -
 Brown, 1-30-97, 3/4" Re-Rod in Monument Box
 Brown, 11-19-97, 3/4" Re-Rod in Monument Box
 L.C.R.C. - NONE
 County Surveyor Records -
 April 13th, 1910
 Survey shows Corner

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-13
 SW Cor, Section 33, T18N-R14E
 Found 3/4" Iron Bar in Monument Box
 Accepted as the best available evidence of original corner position
 (On Kinde Road)


RECORDED

FEB 03 2000

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13
 SW Cor, Section 33, T18N-R14E
 Found 3/4" Iron Bar in Monument Box
 East 178.80' to Monument Box
 N30°E 75.27' to Nail in Power Pole
 N70°W 74.70' to Nail in Telephone Pole
 S10°E 40.35' to Nail in Wood Fence Post
 West 2655.75' to S 1/4 Cor, Sec 32, T18N-R14E
 East 2640.94' to S 1/4 Cor, Sec 33, T18N-R14E



Signed by Charles S. Getz
 Surveyor's Michigan License No. 25843

Date August 16, 1999

PEER GROUP APPROVED AT MEETING R.L.B.
 HELD October 26, 1999