

1999 REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Huron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	Gore T <u>18N</u> R <u>15E</u>	<u>B-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
HURON COUNTY
RECORDED

28 OCT 99 9:17 A.M.

FRANCES L. HOLDWICK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Charles S. Getz, in a field survey on April 14, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

B-13 1834 G.L.O., H. Parke D.S. County Road Commission Records - Iron Pin in Post
 Set quarter section post
 Hemlock 17", N69½°W, 32 Links
 Cedar 9", N40½°E, 48 Links

Recorded Surveys -
 Case, 1-20-72, Liber 1, Page 130, Iron Pin
 Case, 3-2-73, Liber 1, Page 415, Iron Pin
 Brown, 5-15-97, Liber 5, Page 186, Iron Pin in Mon. Box

L.C.R.C. - NONE

Unrecorded Surveys -
 Brown, 8-10-94, 3/4" Steel Stake in Monument Box

County Surveyor Records -
 NONE


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-13
 S 1/4 Cor, Section 31, T18N-R15E
 Found 3/4" Iron Bar in Monument Box
 Accepted as the best available evidence
 of original corner position
 (On Kinde Road)

RECORDED
 FEB 2 1999
 SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-13
 S 1/4 Cor, Section 31, T18N-R15E
 Found 3/4" Iron Bar in Monument Box
 West 25.85' to Monument Box
 S15°W 30.90' to Stop Sign
 N35°W 88.33' to Nail in Power Pole
 N60°W 37.10' to East Leg of Road Sign
 North 31.30' to Culvert
 N70°E 84.40' to Nail in Telephone Pole
 West 2645.87' to SW Cor, Sec 31, T18N-R15E
 East 2650.30' to SE Cor, Sec 31, T18N-R15E



Signed by Charles S. Getz
 Surveyor's Michigan License No. 25843

Date August 21, 1999

PEER GROUP APPROVED AT MEETING
 HELD October 26, 1999. R.L.B.