

Re-Mon. Liber 2, Page 24

1999 REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in GORE Township

Huron
(County)

Located in: Corner Code #

- 1. Public Land Survey T 18N R 15E E - 13
T ----- R -----
T ----- R -----
T ----- R -----
- 2. Property Controlling S T ----- R -----
in Section S T ----- R -----
- 3. Miscellaneous S T ----- R -----
Property in Sec. S T ----- R -----

STATE OF MICHIGAN
HURON COUNTY
RECORDED

30 DEC 99 2:13 P.M.

FRANCES L. HOLDWICK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

SECTION

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Russell L. Brown, in a field survey on July 1, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1834 GLO H. Parke D.S. Set Post Corner Sections 32 and 33, Hemlock 11 N67E 7 1/2, do. 7 N67W 6
County Surveyors Records None
County Road Commission Records None

L.C.R.C. None: Recorded Surveys 8-31-78, Liber 3, Page 674, Huron Surveying Inc. Russell L. Brown P.S. 24588, Found 1/2" Rod Witnesses: N10°W 40.26' Spike in Fence Post, S10°W 57.25' Spike in Tree, S10°E 57.69' Spike in Tree, NOTE: 1/2" Rod referred to in Liber 3, Page 674 was incorrectly used as Corner common to Sections 32 and 33. 1/2" Re-Rod was actually Corner Common to Sections 4 and 5, T17N-R15E, Unrecorded Surveys: 11-1-88, Huron surveying Inc. Russell L. Brown P.S. 24588, Set R.R.S. G.L.O. map offset from N.W. Cor. Sec. Frac. 4, T17N-R15E, West 38.28' 1/2" Re-Rod (N.W. Cor. Frac. Sec. 4, T17N-R15E)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original Corner or Accessories Found.

Found R.R.S. 38.28' East of 1/2" Re-Rod in Monument Box, apparent N.W. Corner Fractional Section 4, T17N-R15E, accepted R.R.S. as best evidence of original corner position.

Removed R.R.S., Set 1/2" x 18" capped Iron in Monument Box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E - 13 Corner Common to Sections 32 and 33, T18N-R15E

Set 1/2" x 18" Steel Stake capped P.S. 24588 and Monument Box

N50°W 56.12' P.K. Nail, N.E. side Wood 4" x 4" Ped. Post


South 25.57' 1/2" x 18" Re-Rod

N55°E 104.36' Spike N.W. Side Power Pole

West 38.28' 1/2" Re-Rod in Monument Box, Apparent North Corner of Sections 4 and 5, T17N-R15E

East 2622.81 to F 13, South 1/4 Section 33, T18N-R15E,

West 2645.42 to D 13, South 1/4 Section 32, T18N-R15E



Signed by Russell L. Brown

Surveyor's Michigan License No. 24588

Date Dec 27, 1999

Peer group approved at meeting held 12-27-99, RLB