

Re Mon. Liber 2, Page 41

1999 REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in PORT AUSTIN Township

<u>Huron</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T 19N R 12E	J - 13
	T-----R-----	
	T-----R-----	
	T-----R-----	
2. Property Controlling S in Section S	T-----R-----	
	T-----R-----	
3. Miscellaneous S Property in Sec. S	T-----R-----	
	T-----R-----	

STATE OF MICHIGAN  
HURON COUNTY  
RECORDED

30 DEC 99 2:16 P.M.

FRANCES L. HOLDWICK  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

SECTION

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Russell L. Brown, in a field survey on Dec. 21, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 1834 G.L.O. H. Parke D.S. Set quarter Section Post, Hemlock 26 N45 1/2W 30; Do. 7 N88 1/2"E 21 1/2  
 County Surveyors Records - None  
 County Road Commission Records - None  
 L.C.R.C. - None  
 Recorded Surveys - None  
 Unrecorded Surveys - None

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 No evidence of original corner or accessories found.

Set 1/2" x 18" Steel Stake capped P.S. 24588 G.L.O. distance from corner K-13, South Corner Sections 35 and 36, T19N-R12E, as best evidence of original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 J-13, South 1/4 Corner Section 35, T19N-R12E  
 Set 1/2" x 18" Steel Stake capped P.S. 24588  
 WITNESSES  
 East 30.22' to Spike in South Side of 22" Oak  
 N45°E 21.28' to Spike in Northeast side of 13" Oak  
 N70°W 36.91' to Spike in Northerly side of 37" Maple  
 S10°W 70.95' to Spike in Easterly Side of 10" Oak  
 East 2640.00' to K-13, South Corner Sections 35 and 36, T19N-R12E

Signed by Russell L. Brown  
Surveyor's Michigan License No. 24588

Date DEC, 27, 1999



Peer group approved at meeting held 12-27-99, RLB