

Re-Mon. Lib 2, Page 35

1999 REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in PORT AUSTIN Township

Huron (County)	Located in:	Corner Code #
1. Public Land Survey	T 19N R 13E	F - 13
	T ----- R -----	
	T ----- R -----	
	T ----- R -----	
2. Property Controlling S in Section S	T ----- R -----	
	T ----- R -----	
3. Miscellaneous S Property in Sec. S	T ----- R -----	
	T ----- R -----	

STATE OF MICHIGAN  
HURON COUNTY  
RECORDED  
30 DEC 99 2:15 P.M.  
FRANCES L. HOLDWICK  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

SECTION

I, Russell L. Brown, in a field survey on Dec. 9, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
1834 G.L.O. H. Parke D.S., Set quarter Section post, Ironwood 16 N56E 22, Hemlock 18 N63 1/2W 22  
County Surveyor Records - None  
County Road Commission Records - None  
L.C.R.C. - none  
Recorded Surveys - None  
Unrecorded Surveys -11-10-88, Huron Surveying Inc. Russell L. Brown P.S. 24588, Set 1/2" Re-Rod 20.13' East of North 1/4 Corner Section 4, T18N-R13E, WITNESSES: N45°W 58.25' to Spike in Southwest side power pole N10°W 34.05' to Spike in East Side Wood Post, N45°E 47.0' to 1/2" Steel Stake

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
No evidence of original corner or accessories found.

Found 1/2" Steel Stake.

Accepted 1/2" Steel Stake as best evidence of original corner position.

Capped Found 1/2" Steel Stake P.S. 24588

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13, South 1/4 Corner Section 33, T19N-R13E

Found 1/2" Steel Stake Capped P.S. 24588

WITNESSES:

North 17.03' to 1/2" Steel Stake

South 19.15' to 1/2" Steel Stake

West 20.11' to 3/4" Steel Stake, apparent North 1/4 corner Section 4, T18N-R13E

N45°W 58.34' to Spike in Southwest side Power Pole


East 2630.06' to G-13, Southeast Corner Section 33, T19N-R13E

West 2634.50' to E- 13, Southwest Corner Section 33, T19N-R13E

Signed by Russell L. Brown

Surveyor's Michigan License No. 24588

Date Dec. 27, 1999



Peer group approved at meeting held 12-27-99 RUB