

Re-Mon. Liber 2, Page 48

1999 REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in PORT AUSTIN Township

<u>Huron</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T 19N R 14E	C - 13
	T-----R-----	
	T-----R-----	
	T-----R-----	
2. Property Controlling S in Section S	T-----R-----	
	T-----R-----	
3. Miscellaneous S Property in Sec. S	T-----R-----	
	T-----R-----	

STATE OF MICHIGAN
HURON COUNTY
RECORDED
30 DEC 99 2:18 P.M.
FRANCES L. HOLDWICK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

SECTION

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		B		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Russell L. Brown, in a field survey on Nov. 1, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1834 G.L.O. H. Parke D.S. Set Post Corners Sections 31 and 32; Sugar 10 N61W 4 1/2; Hemlock 9 N54E 17
County Surveyors Records - None
County Road Commission Records - None
L.C.R.C. - None
Recorded Surveys: - None
Unrecorded Surveys - None

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
No evidence of original corner of accessories found.

Found Cut Grindstone with 3/4" Steel Stake on South Side of Stone

Accepted High Point of cut Grindstone as best evidence of original corner position, raised with 1/2" x 18" Iron Capped P.S. 24588.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-13 South Corner Sections 31 and 32, T19N-R14E
Set 1/2" x 18" Iron Capped P.S. 24588 over high point of cut Grindstone

WITNESSES:

N45°E 36.60' to Notch in North End 24" C.M.P.
S70°E 101.05' to Spike in North Side of Power Pole
S60°W 45.28' to Notch in East End of 18" C.M.P.
N45°W 52.52' to Spike in Northwest Side Power Pole
N60°W 2.35' to 5/8" Steel Stake
East 2641.56' to D-13, South 1/4 Corner, Section 32, T19N-R14E
West 2645.23' to B-13, South 1/4 Corner, Section 31, T19N-R14E

Signed by Russell L. Brown
Surveyor's Michigan License No. 24588

Date DEC. 27, 1999



Peer group approved at meeting held 12-27-99, RLB