

Re-Mon. Liber 2, Page 49

1999 REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in PORT AUSTIN Township

<u>Huron</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T 19N R 14E	D - 13
	T ----- R -----	
	T ----- R -----	
	T ----- R -----	
2. Property Controlling S in Section S	T ----- R -----	
3. Miscellaneous S Property in Sec. S	T ----- R -----	
	T ----- R -----	

STATE OF MICHIGAN
HURON COUNTY
RECORDED

30 DEC 99 2:18 P.M.

FRANCES L. HOLDWICK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

SECTION

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Russell L. Brown, in a field survey on Nov. 6, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1834 G.L.O. H. Parke D.S., Set quarter Section Post, Hemlock 28 N63W 16, Do. 16 N38E 24
County Surveyors Records - None
County Road Commission Records - None
L.C.R.C. - None
Recorded Surveys - None
Unrecorded Surveys - None

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
No evidence of original Corner or accessories Found.

Set 1/2" Dia. x 36" Iron Capped P.S. 24588 by single proportionate measurement between Corners C - 13 and E - 13 as best evidence of original Corner Position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
D-13 S. 1/4 Corner Section 32, T19N-R14E
Set 1/2" Dia. x 36" Re-Rod and capped P.S. 24588
WITNESSES
S35°W 165.03' to 1/2" x 18" Steel Stake
N30°W 177.01' to 1/2" x 18" Steel Stake
S80°W 164.13' to P.K. Nail in Northerly side of Power Pole
West 128.62' to 1" Pipe at apparent North 1/4 Corner Section 5, T18N-R14E
West 2641.56' to C - 13, S.W. Corner Section 32, T19N-R14E
East 2641.55' to E - 13, S.E. Corner Section 32, T19N-R14E

Signed by Russell L. Brown
Surveyor's Michigan License No. 24588

Date Dec 27, 1999



Peer group approved at meeting held 12-27-99. RUB