

Re-Mon. Liber 2, Page 54

1999 REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in PORT AUSTIN Township

<u>Huron</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T 19N R 14E	H-13
	T ----- R -----	
	T ----- R -----	
	T ----- R -----	
2. Property Controlling S in Section S	T ----- R -----	
	T ----- R -----	
3. Miscellaneous S Property in Sec. S	T ----- R -----	
	T ----- R -----	

STATE OF MICHIGAN
HURON COUNTY
RECORDED

30 DEC 99 2:19 P.M.

FRANCES L. HOLWICK
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

SECTION

I, Russell L. Brown, in a field survey on Dec. 7, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1834 G.L.O. H. Parke D.S. Set quarter Section Post, Beech 11 N66E 13, Do. 14 N20W 23
County Surveyors Records - None
County Road Commission Records - None
L.C.R.C. - None
Recorded Plats: 1953 Bald Eagle Point Subdivision, Liber 4 of Plats, Page 57, Galen W. Case # 7431
No object stated, or accessories given
1955 Bald Eagle Pint Subdivision No. 2, Liber 5 of Plats, Page 17, Galen W. Case # 7431
No object Stated or accessories given.
Recorded Surveys - None Unrecorded Surveys - None

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
No evidence of original corner or accessories Found.

Set 1/2" x 18" Steel Stake capped P.S. 24588, G.L.O. measurements from corner G- 13 as best evidence of original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
H-13, South 1/4 Corner Section 34, T19N-R14E
Set 1/2" x 18" Steel Stake Capped P.S. 24588
WITNESSES:
S75°W 29.27' to N.E. Corner of Concrete Block Foundation of Cottage # 7777
S80°E 23.44' to N.W. Corner of Concrete Block Foundation of Cottage # 7771
N20°E 19.40' to Spike in Westerly Side of 15" Maple
S25°E 62.79' to Spike in West Side of 13" Cherry
East 1099.93' to Witness Corner to the meander corner
West 2640.00' to G-13, South Corner of Section 33 and 34, T19N-R14E

Signed by Russell L. Brown
Surveyor's Michigan License No. 24588

Date Dec 27, 1999



Peer group approved at meeting held 12-27-99. RLB